



Agenda # 12
Commission Meeting Date:
October 21, 2014

**CITY OF GREAT FALLS
COMMISSION AGENDA REPORT**

Item: Professional Services Contract Amendment: Water Treatment Plant Facility Upgrades, O. F. 1519.0

From: Engineering Division

Initiated By: Public Works Department

Presented By: Jim Rearden, Public Works Director

Action Requested: Approve Professional Services Contract Amendment

Suggested Motion:

1. Commissioner moves:

“I move the City Commission approve the Professional Services Contract Amendment between the City of Great Falls and Black and Veatch Corporation for engineering services for the Water Treatment Plant Facility Upgrades, O. F. 1519.0 for a fee not to exceed \$4,474,649.00, and authorize the City Manager to execute the agreements.”

2. Mayor calls for a second, discussion, public comment, and calls for the vote.

Staff Recommendation: Approve Professional Services Contract Amendment.

Background:

Significant Impacts

City Staff entered into a professional services contract with Black and Veatch in July of 2012 to evaluate and design infrastructure upgrades recommended at the Water Treatment Plant (WTP) from the 2006 Water Master Plan. During the evaluation of existing facilities multiple items were identified to be added into the scope of the project. The most significant design additions include equipping the Ultraviolet (UV) Treatment system, removal of the seasonal clearwell, addition of a surge tank, replacement of the Northwestern Energy substation and increasing facility sizing to preserve the plant maximum hydraulic capacity of 66 MGD. Design features to accommodate future improvements, such as suction piping and a utility tunnel to accommodate future backwash supply pumps, will also be included in the design.

Items were also removed from the original scope of the project to address affordability concerns. Reductions in scope include eliminating the Machine Shop, Low Service pump upgrades, postponing the replacement of the Motor Control Centers and making the

Administration Building an optional item.

The changes in scope will result in an approximate doubling in the costs associated with the construction scope and design services. The original design contract was \$2,562,715.00. The current proposed design services are listed as \$5,244,138.00. There are \$769,489.00 remaining in the current contract which will be used for final design, reducing the contract amendment value to \$4,474,649.00.

Workload Impacts

Black and Veatch, along with their partner firms Thomas Dean and Hoskins (TD&H) and L'Heureux Page Werner (LPW), will proceed with the design and the construction phase of the upgrades identified during the evaluation and conceptual design phase. City engineering and WTP staff will assist with project administration duties.

Purpose

The work originally considered by this contract focused on items identified in the 2006 Water Master Plan. These items included designing replacement of the over 50 year old electric switch gear with more reliable, redundant and serviceable equipment, designing a new administration building, designing a new chemical feed building with an ammonia feed system, designing the replacement of low service pumps and building a wall around the electrical substation to address vulnerability concerns.

During the detailed evaluation of these items at the WTP, other components of the treatment system were identified for improvement. The first of these was the addition of a UV Treatment system in the first phase of improvements. The City conducted a filter study at the WTP to determine if improvements to the existing system could be made to reach compliance with the Long Term 2 Enhanced Surface Water Treatment Rule. The result of this study combined with staff operation experience indicated that the current facilities could not reliably meet the new rule standards and that UV treatment would be required by the Montana Department of Environmental Quality. The selection and design of a UV treatment system was added to the design effort in order to meet the new rule requirements. With the installation of a new UV system, a surge tank must be designed to relieve pressure that could damage the UV system. An upsized surge tank will replace the existing seasonal clearwell that was recently identified for replacement during a condition analysis.

The next major item that was added to the design project was the replacement of the Northwestern Energy Substation. During the evaluation of the substation, the age and location were identified as risks. Replacing the substation in an enclosed area with new equipment was identified as an improvement that would increase the reliability of the power feed to the WTP.

With the improvements identified above and other lesser items that were identified, the project construction cost estimate grew from an original estimate of 10 to 12 million dollars to an updated estimate of 25 million dollars. With this increase in scope and construction cost, the engineering fees for the completion of design and construction management services also increased significantly.

Project Work Scope

The Black and Veatch team will proceed with the final design phase of the accepted infrastructure upgrades and conduct bidding and construction phase services for the project. Bidding is currently scheduled for January of 2016 with construction starting in the spring of 2016.

Initial Evaluation and Selection Process

The team led by Black and Veatch was selected for this project based on the engineering selection policy used by the City of Great Falls. An invitation to submit proposals was advertised in the Tribune detailing the project, selection process, submittal deadline and interview dates. Two consultant teams submitted written proposals and each gave a presentation to a selection committee of Public Works staff. Based on these proposals and presentations, the Black and Veatch/ TD&H/ LPW team scored the highest based on their ability to complete the work and past performance with similar projects. The professional services contract was then negotiated. Black and Veatch is a national firm with the majority of their work to be carried out by its offices and staff located in Denver, Colorado and Kansas City, Missouri. TD&H is a Great Falls based firm with offices located throughout Montana and neighboring states. TD&H's workload will be completed entirely by staff located in Montana. LPW is a Great Falls based architecture firm and their workload will be completed by staff located in Great Falls.

Conclusion

City staff recommends approval of the Professional Services Contract Amendment No. 1 to Black and Veatch in the amount of \$4,474,649.00.

Fiscal Impact

This contract will be funded through Water Treatment Plant funding secured through a loan from the State Revolving Fund (SRF).

Alternatives:

The City Commission could vote to deny the approval of the Professional Services Contract Amendment No. 1.

Attachments/Exhibits:

1. Professional Services Contract Amendment No. 1.

AMENDMENT NO.1

PROFESSIONAL SERVICES AGREEMENT

OFFICE FILE 1519.0

Great Falls Water Treatment Plant Facility Upgrades

This AMENDMENT made this ____ day of October, 2014 by and between the CITY OF GREAT FALLS (OWNER), and Black & Veatch Corporation (ENGINEER) shall amend the Agreement for Professional Services dated July 17, 2012 between the aforementioned parties, whereby the ENGINEER shall remove an activity authorized by the original contract. Services covered under this amendment pertain to Additional Services tasks provided by the ENGINEER to the City of Great Falls.

Amendments to the original Agreement are as follows:

1. Replace the scope of services and associated fees for the following tasks from the Agreement for Professional Services with the scope of services and fees contained in Attachment A: Task Nos. 310, 320, 330, 340, 345, 350, 360, 361, 410, 420, 430, 440, 450, and 451.
2. Add the scope of services and associated fees for the following tasks contained in Attachment A: Task Nos. 110A, 190D, 190E, 260, 261, 262, 263, 264, 265, 289A, 290A, 294B, 295, 301, 302A, 303, 304, 306, 308, and 425.
3. Perform the scope of services for this Amendment in accordance with the schedule presented in Attachment A.
4. Increase the total not-to-exceed fee of \$2,562,715.00 for the Agreement for Professional Services by \$4,474,649.00 for an amended total not-to-exceed fee of \$7,037,364.00.

IN WITNESS THEREOF, the Parties hereto have executed this Agreement on the ____ day of October, 2014.

CITY OF GREAT FALLS

REVIEWED FOR LEGAL CONTENT

Gregory T. Doyon, City Manager

Sara R. Sexe, City Attorney

ATTEST:

Lisa Kunz, City Clerk

(Seal of the City)

Black & Veatch Corporation

Peter J. Cohlma

Peter J. Cohlma, Vice President

STATE OF COLORADO)

County of Arapahoe : ss.

On this 10 day of October, 2014, before me, a Notary Public in and for the State of Colorado, personally appeared Peter J. Cohlma, known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that he executed the same.

In WITNESS THEREOF, I have hereunto set my hand and affixed my official seal the day and year in this certificate first above written.

Michael Sawyer
Notary Public for the State of

Colorado

Printed Name: Michael Sawyer

My Commission Expires: 3/22/2016

(NOTARIAL SEAL)

**MICHAEL SAWYER
NOTARY PUBLIC
STATE OF COLORADO
NOTARY ID 20044010060
MY COMMISSION EXPIRES 03/22/16**

END

City of Great Falls, Montana

Water Treatment Plant Facility Upgrades, OF 1519.0

Amendment No. 1

Attachment A

Project Description

The Water Treatment Facility Upgrades Project (Project) has been broken down into a number of phases to be constructed over time. The engineering services described herein are for Phase 1 of the Water Treatment Facility Upgrades. Phase 1, including the two alternate bid items, is defined in the preliminary drawings prepared for Task 282C and presented in Appendix A. The floor plan of the Administration Building Addition and the site plan was revised to reflect the review comments received from the City of Great Falls (Owner) at the August 27, 2014 Review Meeting and the revised floor and site plans are presented in Appendix A. Alternate Bid Item No. 1 is the replacement of the NW Energy Substation and Alternate Bid Item No. 2 is the construction of the Administration Building Addition.

Other features of the Phase 1 Project include: 1) The Chemical Feed and UV Disinfection Building will be designed to accommodate the installation of the Merrick Storage and Feed System for lime in a future phase, 2) The Owner has selected the Wedeco K143 12/5(6) UV Reactor for inactivation of Cryptosporidium and Giardia, 3) A utility crossing of the existing railroad line will require coordination with the BNSF Railroad, 4) Industrial Automation Consulting, Inc. (IAC) has been selected by the Owner to provide the programming and integration services for Phase 1.

The preliminary list of drawings for Phase 1 is shown in Appendix B and the Table of Contents for the Project Manual is shown in Appendix C. Drawings will be prepared using the Revit software. The 2013 Engineers Joint Contract Documents Committee front end and technical specifications and Black and Veatch's BIM Workflow Model will be used for the Project.

Existing Medium Voltage Motors, Motor Starters and Cables Condition Assessment

Some of the existing medium voltage motor starters and cables for the Low and High Service Pumps were installed in 1959 with others being installed more recently. Included as part the Project is the replacement of the existing medium voltage motors, motor starters, and cables for the Low Service Pumps and the existing medium voltage motor starters and cables for the High Service Pumps. This upgrade, however, has been deferred to a future phase and the existing equipment will be used in the Phase 1 of the Project.

A condition assessment of the existing medium voltage motors, starters and cables will be conducted for the purpose of identifying problems that can be corrected as part of Phase 1. The intent is to prolong the life and improve the reliability of the existing equipment.

Hazardous Materials Assessment

A pre-renovation and pre-demolition asbestos inspection must be completed in accordance with Administrative Rules of Montana (ARM) 17.74.354, and in accordance with National Emissions Standards for Hazardous Air Pollutants (NESHAP), which require that an asbestos inspection be completed prior to a planned renovation or demolition of any facility or portion thereof.

Programmable Logic Controller Migration Plan and Performance Test of Partial Conversion

The Water Treatment Plant Facility Upgrades Project includes the installation of new programmable logic controllers (PLCs) for new equipment and replacement of some of the existing PLCs. The existing PLCs used at the water treatment plant (WTP) and remote sites are a mixture of GE 90-30 and GE Versamax Micro PLCs. The existing PLCs in the WTP are about 15 years old and the GE 90-30 PLCs are expected to be obsolete in the near future. For the long term, new PLCs will be needed to replace existing ones. In response to this situation, the Owner wants to develop a plan to migrate the existing PLC system to one of a modern platform.

The manufacturer of the existing PLCs has developed a new PLC, the GE PACSystem™ RX3i (RX3i). The RX3i has the capability to communicate with the existing PLCs and it can be used as a direct replacement for the existing 90-30 PLCs.

The Owner has selected the GE PACSystem RX3i as the manufacturer and model of the new PLCs for the WTP Facility Upgrade Project.

The migration plan is to determine how and when the existing PLCs need to be replaced and present the estimated construction costs for installing the new PLCs. To test the concept of incorporating the RX3i PLCs into the existing system, a partial conversion to a new PLC and subsequent performance tests of the conversion will be conducted. The partial conversion will consist of converting the existing Filter Building 90-30 PLC program to run on a GE RX3i PAC. The performance tests will be conducted through off-site bench-top testing. The existing Filter Building 90-30 PLC has been chosen for the partial conversion and performance test for the following reasons:

1. The filter building 90-30 has the most complex communications. It uses a programmable communications card with a custom program written in basic by Horner Electric that allows the PLC to be a Modbus Master. The card will be eliminated and the RX3i will become the new Modbus Master and it needs to directly interface with the MDS 9790B master radio in the control room. The RX3i will require some new programming to make that connection work. Without doing that first it cannot communicate with the RTUs that will be involved with the partial migration.
2. Almost all of the data used by the HMI and Historian in the Control Room is read or written to the 90-30 in the Filter Building now. The RX3i replacing the 90-30 will need to do the same. The HMI application will be changed to some extent, as will the PLC program, to duplicate that functionality. Again, the partial migration will depend on this part of the SCADA system working.

3. The RX3i at the Filter Building will need to demonstrate that it can reliably communicate with the different types of PLCs used in the RTUs. These include 90-30, Versamax, and other RX3i PLCs.
4. The 90-30 in the filter building has a lot of local I/O that will be moved to new Bases. As soon as the converted 90-30 program is installed in the RX3i, all of the I/O needs to be tested and validated.
5. Rather than work from the “outside in”, meaning that RTUs are converted before the Master PLC, it would be prudent to get the core of the SCADA system (Master radio, Master PLC, HMI, and Historian) converted and working first and then move on to the RTUs.

As part of the migration plan the existing radio telemetry system will be evaluated to identify any potential deficiencies that would need to be addressed as part of PLC migration plan.

The Owner currently has the following PLCs in service:

WTP PLCS	REMOTE SITE PLCS
Filter Building Control Room	33rd Street Booster
Chlorine Room	Skyline Elevated Tank
Backwash Clarifier	Ella Elevated Tank
Headhouse	Gore Hill Booster Station ¹
	Gore Hill Elevated Tank
	Boston Heights Standpipes
	MAFB Flow Meter Pit
	Fire Station 1 Basement

1. The Boston Heights Components may be removed as this will be taken out of service.

Scope of Services

This scope of services specifically excludes services for detailed design, bidding, construction and commissioning phases for the improvements identified in:

- Task No. 262 – Develop Migration Plan for PLC Conversion
- Task No. 264 – Perform a Partial Conversion of Existing System to a RX3i PLC Based System and Test Performance
- Task 301 – Conduct Hazardous Materials Assessment
- Task 308 – Testing of Electrical Grounding

Detailed Design and Bidding Phase

Task 110A - Amend Project Work Plan

Activities

Distribute critical success factors; baseline scope; schedule; budget; staffing plan; communication plan; Quality Control Review Comment Procedures; Choice, Change, and Decision Impact on Baseline Project Scope, Schedule and Cost Register Procedures; and QA/QC plan to Owner and Consultant project team.

Deliverables

Electronic copy of Project Work Plan

Task 190 D – Continued Project Management & Controls

Deliverables

- Bi-Weekly Progress Meetings and Schedule Updates via Telephone
- Monthly Invoicing and Budget Status
- Updates to the Choice, Change, and Decision Impact on Baseline Project Scope, Schedule and Cost Register

Task No. 260 – Review Existing Documents & Data

Activities:

- Review information that Industrial Automation Consulting, Inc. (IAC) has on the existing system and determine the gaps in the information.
- Gather drawings and information on the existing control systems at the Water Plant, including those in the Filter Building, Pump Station, Head House, and Backwash Clarifier.
- Gather drawings and information for the remote sites comprising the water system infrastructure including Fire Station 1, Malmstrom AFB, Boston Heights, 33rd St, Ella, Gore Hill, and Skyline. These sites are generally either water storage structures, pump stations, or pressure/flow monitoring stations.

Information and Support from Owner:

- Electronic copy of Control Block Diagram/System Architecture, P&IDs, and schematics of existing control system.

Task No. 261 – Prepare As-built Drawings for Existing SCADA System

Activities:

- Conduct site visits to WTP and remote sites to review changes and confirm configuration of existing system.
- Where it is determined that the as-built documentation is incomplete, inaccurate, or simply unavailable, conduct additional site visits as required to obtain the information necessary for complete as-builts.
- Develop as-built drawings for the entire Supervisory Control and Data Acquisition (SCADA) system, end to end.
- Depending on the magnitude of the as-builts task, allow deferring some of the Work until a later time provided that it does not impede the migration to the RX3i PAC platform at the Filter Building.
- Prepare as-built drawings including Control Block Diagram/System Architecture, P&IDs, and schematics.

Deliverables:

- Electronic copy of as-built Control Block Diagram/System Architecture, P&IDs, and schematics.

Information and Support from Owner:

- Services of a technician employed by the Owner who has intimate knowledge of the SCADA system to assist with gathering information needed for the as-builts.

Task No. 262 – Develop Migration Plan for PLC Conversion

Activities:

- Develop a migration plan for effecting the change from the existing PLCs to the PACSystem RX3i PLCs, including an implementation plan that is phased over time. The migration plan will be based on the information and schematics on the existing SCADA system shown in Appendix D.
- Provide value engineering to determine where a different GE PLC platform, such as the GE Versamax or Durus PLC, would be more cost effective and appropriate replacement for certain existing PLCs than the RX3i, while satisfying all communications and control requirements.
- Address integration with HMI, changes to tagging structure, and communications.
- Define how the existing PLCs are to be replaced and what other control system modifications will be needed to accommodate the change in PLCs.
- Determine where the RX3i PAC, Versamax PLC, Durus PLC or other GE PLC platform should be used.
- Determine the protocols that are most suitable for each type of communications link used by the SCADA system.
- Evaluate the existing telemetry system including the Master telemetry radio, Repeater, and everything communicating with the Repeater (i.e., the 9710b and 9810b radios).
- Develop the performance requirements for any new telemetry equipment that will be used by the SCADA system.
- Develop a plan for what to do with the telemetry system, and define the steps involved with getting it done.
- Define the benefits and possible risks associated with replacing the telemetry system.

- Obtain accurate GPS coordinates and antenna heights for all telemetry antennas and towers.
- Conduct a complete software based radio path study.
- Prepare Summary Memorandum to include results of evaluations and recommendations for conversion of the existing PLCs.

Deliverables:

- Electronic copy of Summary Memorandum.

Information and Support from Owner:

- Consolidated, written review comments on summary memorandum.

Task No. 263 – Migration Plan for PLC Conversion Review

Activities:

- Review Migration Plan for PLC Conversion.
- Select preferred approach for migration.

Deliverables:

- Review workshop at Owner facilities.
- Review workshop agenda and minutes.

Task No. 264 – Perform a Partial Conversion of Existing System to a RX3i PLC Based System and Test Performance

Activities:

- Convert the Filter Building 90-30 PLC program to run on a GE RX3i PAC.
- Through bench-top testing, verify that the Wonderware Intouch application running on the HMI computer in the Filter Building Control Room is exchanging data properly with the Filter Building RX3i PAC.
- Through bench-top testing, verify that the Historian application running on computers in the Filter Building is still referencing the correct data in RX3i PAC as previously referenced in the 90-30 PLC.
- Through bench-top testing, verify that all real-time/historical trends displayed by the Historian for the previous 90-30 are still functioning properly with the RX3i PAC.
- After successfully migrating the Filter Building RX3i PAC, perform a similar bench-top test of the conversion/migration for a single RTU that is in direct communications with the Filter Building RX3i PAC.
- If a controller other than the RX3i PAC, such as the GE Versamax PLC, will be used as a 90-30 PLC, perform a migration to the alternate platform and validate the results.
- Prepare an opinion of probable construction costs (OPCC) for conversion of the existing PLCs.
- Amend the Migration Plan for PLC Conversion to incorporate the results and recommendations of the performance test of the partial conversion and to include the OPCC for conversion of the existing PLCs. The OPCC will be a Class 3 Estimate as defined by the Association for the Advancement of Cost Engineering.

Deliverables:

- Converted Filter Building 90-30 PLC program.
- Converted 90-30 PLC or VersaMax PLC program.

- If modifications are required to the Wonderware Intouch HMI application for the Filter Building control room the updated application will be provided.
- If modifications are required to data Historian and Historian Client applications the updated applications will be provided.
- Opinion of Probable Construction Costs to migrate the existing PLC system to an RX3i PLC based system.
- Amended Migration Plan.
- Electronic copy of amended Summary Memorandum.

Information and Support from Owner:

- Consolidated, written review comments on summary memorandum.
- All RX3i PAC, Rxi PAC, and alternate platform components furnished by Owner.
- Proficy Machine Edition programming Software for the PAC platform and alternate platforms furnished by the Owner.

Task No. 265 – Partial Conversion of Existing System and Performance Test Review

Activities:

- Review results of partial conversion and performance test.
- Review revised summary memorandum.

Deliverables:

- Conference call.
- Electronic copy of conference call agenda and minutes.

Task 289A - Owner Commission Presentations

Activities

Present Preliminary Engineering Report and Proposal for Detailed Design and Construction Phase Services to Owner Commission.

Deliverables

Two Owner Commission presentations.

Task 290A –Continued Determination of Location of Existing Buried Utilities

Continuation of hydro-vac excavation of assumed buried utility locations beyond those identified in the fall of 2013. Approximately 75 utilities are identified for exposure and field measurement. The initial locations of the buried utilities will be based on historical records and are only as accurate as the information available. This task does not ensure that we have accurately depicted all buried utilities.

Activities

- Identification of locations where existing piping, direct buried conduits, ground cables, handholes, and electrical duct banks is to be potholed and exposed.

- Inspection of external condition of exposed piping, ground wires, conduits, handholes, and duct banks.
- Surveying to determine coordinates and elevation of exposed pipe, conduits, and duct banks.

Deliverables

Horizontal locations and elevation of exposed pipe, conduits, flume and duct bank.

Information and Support Provided By Owner

- Equipment and labor to excavate and expose existing piping, conduits and ductbank, and backfill of excavation.
- Coordination with survey.

Task 294B – Continued Coordination with NW Energy

Initial authorization for services performed on a time and materials basis has been expended.

Continued coordination is necessary to resolve conceptual design issues.

Black & Veatch proposes to spend up to 708 hours of professional time in coordinating with NW Energy to work through the modifications and/or replacement of the existing substation on a time and materials basis. The estimated fee associated with the 708 hours of time is \$105,336. Estimated travel related expenses are \$14,124. The total fee is 119,460. This work will be performed on a time and materials basis.

Activities:

- Coordinate with NW Energy to obtain information needed: for design of the WTP electrical system, and either modification or replacement of the existing substation; and to resolve access into substation, required substation and easement area, service disconnect and metering facilities, physical dimensions and layout of the facilities.

Information and Support Provided By Owner:

- The Owner will contract with NW Energy to provide engineering services, cost estimates, drawings, layouts, specifications, information, and to coordinate with Black & Veatch.

Task 295 – Review of Design Deliverables by Industrial Automation Consulting

Activities

- Industrial Automation Consulting (IAC) will review and provide comments on the Phase 1 Drawings; and the 15%, 30%, 60% and 90% Detailed Design Documents.
- IAC will review P&ID drawings, control panel related drawings and specifications, instrument detail drawings, and specifications (narratives, loops, equipment).
- IAC will provide information on the Owner preferences for instrumentation and control features and equipment.

- IAC will participate in conference calls to answer questions, provide input and clarify review comments.

Deliverables

Electronic copy of review comments on design deliverables and information on instrumentation control features and equipment.

Task 301 – Conduct Hazardous Materials Assessment

The only hazardous materials anticipated are lead in paint and asbestos. An asbestos and lead paint inspection will be performed for the areas anticipated to be included in any future renovation.

Activities

- Industrial hygiene staff accredited as asbestos inspectors through the Montana Department of Environmental Quality (MDEQ) will perform the asbestos inspection of the interior and exterior of the buildings.
- The number of samples collected is dictated by law based on the number of homogeneous areas of suspect ACM. Based on a site visit, we have assumed the total number of bulk samples to be collected will not exceed 120 on a layer basis. The bulk buildings material samples will be shipped under chain-of-custody protocol to a laboratory recognized by the MDEQ and accredited under the National Voluntary Laboratory Accreditation Program (NVLAP) for analysis using polarized light microscopy (PLM) for asbestos. Repair of sampling locations other than any minimal encapsulation necessary to prevent release of asbestos fibers will not be performed.
- In addition to field inspection and lab testing for asbestos materials, provide a document review of all available design drawings, as-recorded drawings, specifications and reports in search of indications asbestos-concrete (AC) pipe exists within the treatment plant site. Findings will ultimately be included in the investigation report including exhibits illustrating the pipe location, size and any other information identified in the research.
- Assess lead in paint using an X-ray fluoroscope (XRF). This instrument is the primary lead survey tool in accordance with the guidance developed by the U.S. Department of Housing and Urban Development (HUD) and applicable to work place safety regulations of the Occupational Safety and Health Administration (OSHA). Occasionally, interferences result in inconclusive XRF readings that require collection of paint chips for laboratory analysis. For purposes of this proposal, it is assumed that there will be no inconclusive result. The LBP data obtained during the inspection will be adequate to determine the proper handling and disposal of buildings components with LBP.
- To the extent feasible, inspect all areas for suspect materials. However, inaccessible spaces, potentially including confined spaces, may require additional investigation in the future when they become accessible. Areas not included in the inspection survey and/or sampling program will be identified in the report.
- A single report will be prepared to include the areas affected by the plant upgrade. Figures will be drafted to show sampling locations and locations of hazardous materials. Recommendations will be provided based on the survey results.

- Prepare mitigation opinion of construction cost estimates that are as concise as possible based on as-built documents and the results of the hazardous materials survey. Cost opinions will be a Class 5 Estimate as defined by the Association for the Advancement of Cost Engineering.

Deliverable(s)

- Electronic copy of report summarizing the results of the investigation and including an Opinion of Probable Construction Costs.

Information and Support from Owner

- Provide access to all existing facilities and specific locations identified for sample collection.

Task 302A – Continued Permitting Assistance and Coordination with Montana Department of Environmental Quality

Black & Veatch proposes to spend up to 468 hours of professional time in coordinating with MDEQ on the permitting related activities for the WTP Facilities Upgrade. The estimated fee associated with the 468 hours of time is \$74,744. Estimated travel related expenses are \$4,504. The total fee is \$79,248. This work will be performed on a time and material basis.

Activities

- Coordinate with MDEQ to address comments, provide information, and facilitate permitting of the modifications associated with the WTP Facility Upgrades Project.
- Prepare Public Water Supply Deviation Requests as requested by MDEQ.
- Develop documents that will need to be submitted to MDEQ for UV permit approval, including deliverables noted below.
- Assist MDEQ with development of permit language.
- Remote assistance with pre- or post-permit trial operating period if required by MDEQ.
- As needed SRF loan assistance
- Conduct and attend one four hour long meeting in Helena with MDEQ with two Black & Veatch professionals attending.

Deliverable(s)

- **UV Operations Plan** - Document reviewing the operating strategy and control philosophy for the UV system, specifically reviewing the following topics: (1) Monitoring strategy, algorithm development and UVDGM compliance; (2) Target pathogen and disinfection strategy; (3) Review of UV facility design conditions and treatment capacity; (4) UV system routine operating procedures; (5) Alarm conditions and system responses; (6) Off-specification avoidance, operation and response procedures; (7) Lamp break and mercury release concerns; (8) Maintenance and regular calibration check requirements; (9) Routine monitoring and data recording.
- **Lamp Break Standard Operating Procedure** – Development of standard operating procedures for the in the event of off-line or on-line lamp break events and response to mercury release concerns.

- **Startup/Commissioning Memorandum** – Memorandum outlining results of startup and performance testing confirming proper system operations via comparison of test data to expected performance from the reactor validation.
- **Monthly Reporting Format / Tables** – Development of tables used by Great Falls WTP staff for monthly reporting to MDEQ. Tables will be developed based on the recommendations of the UVDGM and input from MDEQ, modified where necessary to reflect the specific operating parameters of the Wedeco K143 12/3 UV system.
- **List of Spare Parts** – Prepare a list of recommended spare parts to be kept on hand for the UV disinfection system.
- **Recording Keeping** – Prepare a memorandum describing the records to be kept for the operation and maintenance of the UV disinfection system.
- **Safety** – Prepare memorandum outlining safety precautions and procedures for operating, maintaining and cleaning the UV disinfection system.

Information and Support from Owner

- Review and input on draft deliverables above outlined prior to submittal to MDEQ.

Task 303 – On-call Surveying

Black & Veatch proposes to budget \$9,510.00 for professional engineering and surveying tasks associated with miscellaneous topographic surveying not anticipated for typical detailed design activities. This work will be performed on a time and material basis in accordance with contract labor rates and expenses.

Activities

- Office preparation and processing electronic survey files.
- Topographic surveying of surface features for establishing base drawings.

Deliverables

- Electronic copy of topographic maps and field data.

Information and Support from Owner

- Provide access to all existing facilities and specific locations identified for topographic surveying.

Task 304 – Prepare Contractor Information Package for IAC Construction Services

Activities

- Prepare a Contractor Information Package consisting of the scope of services, terms of conditions, and the schedule for performing the services for construction to be included as part of the Project Manual.
- Prepare a list of preferred equipment to be used on the project.
- Prepare a proposal to the Owner containing the scope of services, schedule, fee, and terms of conditions for construction services.

Deliverables

- Electronic copy of draft and final Contractor Information Package
- Electronic copy of draft and final proposal to Owner
- List of preferred equipment

Information and Support from Owner

- Written review comments on the Contractor Information Package consolidated and listed in the Reviewer portion of the Quality Control Review Comments.
- Written review comments on the proposal to Owner consolidated and listed in the Reviewer portion of the Quality Control Review Comments.

Task 306 – Prepare Contractor Information Package for Wedeco K143 12/5(6) UV Reactors

A Contractor Information Package, as defined in Section 13700, Paragraph 1-4.02 of the Project Manual for the UV Light Disinfection Equipment Pre-selection will be prepared and included in the Project Manual for Phase 1 of the Water Treatment Facility Upgrades Project. In addition, the submittal for the UV Disinfection Equipment will be submitted to and reviewed by Black & Veatch. The revised submittal will be included in the Contractor Information Package. The general contractor will be required to submit the revised submittal for approval.

Activities

- Prepare and submit a Contractor Information Package, as defined in Section 13700, Paragraph 1-4.02 of the Project Manual for the UV Light Disinfection Equipment Pre-selection.
- Prepare and submit the Submittal for UV Disinfection Equipment. Submittal to be in accordance with the Project Manual for the UV Light Disinfection Equipment Pre-selection.
- Revise the Submittal and the Contractor Information Package for the UV Light Disinfection Equipment to address review comments from the Owner and Black and Veatch.

Deliverables

- Electronic copy of draft and final Submittal and Contractor Information Package

Information and Support from Owner

- Consolidated, written review comments on the draft Submittal and Contractor Information Package

Task 308 – Testing of Electrical Grounding

Activities

- Perform testing of the electrical grounding of the existing motor starters and motors for the Low and High Service Pumps, motors for the High Service Pumps, and the cables between the motors and motor starters for the Low and High Service Pumps.
- Conduct Fall of Potential Test in accordance with IEEE 81 Standard.

- Conduct point-to-point ground verification for motor starters and motors for Low and High Service Pumps.

Deliverables

- Electronic copy of report summarizing the results of the testing of the electrical grounding..

Information and Support from Owner

- Access to all equipment to perform testing.

Task 310 - 15% Detailed Design & Basis of Design Memorandum

Activities

- Prepare Schematic and Spatial Design Package Containing: Equipment Lists, Process Equipment Info & Control Functions, Process Flow Diagrams, P&IDs and Control Strategy/Descriptions, Control System Block Diagram, Hydraulic Profile, Updated Facility Layouts / Floor plans, Updated Site Plan, Preliminary Geotechnical & Foundation Drain Information, Chemical Storage and Feed Schematics, Chemical Storage and Feed Criteria Tables, Equipment Tagging Standards, Communication Systems, Security Systems, Utility Requirements, Discipline Design Guidelines and Criteria, Consolidated Basis of Design Memo, Topographic Survey of areas that are known to be needed.
- Coordinate with BNSF Railroad on the utility crossing of the existing rail line.
- Investigate location of future sludge line through Bid Alternate No. 2 improvements.
- Conduct a workshop to define control system standards.
- Conduct internal quality control review.

Deliverables

- Control Systems Workshop. Workshop to be four hours long. Two representatives from Black & Veatch and one representative from IAC will attend the workshop.
- Electronic copy of agenda and minutes for Control Systems Workshop
- Electronic copy of 15% Design Package
- 15% Design Review Meeting. Meeting to be four hours long and conducted using Live Meeting. A representative from Black & Veatch, TD&H Engineering and LPW Architects will attend the meeting and other Consultant Team members will participate via Live Meeting.
- Electronic copy of agenda and minutes of Review Meeting
- Electronic copy of Designer Response to Quality Control Review Comments received from Owner on draft Phase 1 Drawings

Information and Support from the Owner

- Written review comments on the 15% design package consolidated and listed in the Reviewer portion of the Quality Control Review Comments.

Task 320 - 30% Detailed Design

Activities

- Prepare 30% Design Package Containing: Front End Contract Documents, Civil/Site Drawings & Details, Geotechnical Report, Final Hydraulic Profile, Facility Equipment & Piping Sections, Process Equipment Specifications, Architectural CAD Plans for Buildings, Architectural Elevations, Major Building Sections, Prelim Structural Design (preliminary foundation, floor and roof plans), Column Row Locations & Floor Elevations, Code Classification Table, Locate HVAC & Plumbing Equipment, Locate Electrical & I&C Equipment, Updated Power Distribution Diagram, Update Control System Block Diagram, Updated P&IDS and Control Descriptions, I&C I/O Lists & Device Schedules, Updated Opinion of Probable Construction Cost (AACE Class 3 Estimate).
- Provide in the specifications a list of the permits that must be obtained by the construction contractor including those for railroad crossings, fire protection, and utility services.
- Conduct internal quality control review.

Deliverables

- Electronic copy of 30% Design Package
- 30% Design Review Meeting. Meeting to be four hours long and conducted using Live Meeting. A representative from Black & Veatch, TD&H Engineering and LPW Architects will attend the meeting and other Consultant Team members will participate via Live Meeting.
- Electronic copy of agenda and minutes of Review Meeting
- Electronic copy of Designer Response to Quality Control Review Comments received from Owner on 15% Design Package

Information and Support from the Owner

- Written review comments on the 30% design package consolidated and listed in the Reviewer portion of the Quality Control Review Comments.

Task 330 - 60% Detailed Design

Activities

- Prepare 60% Design Package Containing: Updated Civil/Site Drawings & Details, Yard Piping & Underground Utility Drawings, Updated Equipment & Piping Floor Plans, Process Equipment Sections & Details, Updated Process Equipment Specifications, Pipe, Valve, Bldg Material, Concrete Specs, Architectural Floor/Roof Plans, Architectural Wall Sections, Architectural Schedules, Structural Foundation and Framing Plans & Sections, Plumbing & Fire Protection System Drawings, Plumbing Schedules, HVAC Plans & Equipment Schedules, Power Plans, Lighting Plans, Electrical Fixture Schedules, Duct Bank & Site Lighting Drawings, Final Equipment Control Descriptions, Final P&IDs, Final I/O Lists, Instrument Device Schedules, Updated Opinion of Probable Construction Cost (AACE Class 3 Estimate).
- Conduct internal quality control review.

Deliverables

- Electronic copy of 60% Design Package
- 60% Design Review Meeting. Meeting to be four hours long and conducted using Live Meeting. A representative from Black & Veatch, TD&H Engineering and LPW Architects will attend the meeting and other Consultant Team members will participate via Live Meeting.
- Electronic copy of agenda and minutes of Review Meeting
- Electronic copy of Designer Response to Quality Control Review Comments received from Owner on 30% Design Package

Information and Support from the Owner

- Written review comments on the 60% design package consolidated and listed in the Reviewer portion of the Quality Control Review Comments.

Task 340 - 90% Detailed Design

Activities

- Prepare 90% Design Package Containing: Complete Front End Documents, Complete Technical Specifications, Complete Drawings & Details, And Updated Opinion of Probable Construction Cost (AACE Class 2 Estimate).
- Conduct internal quality control review.

Deliverables

- Electronic copy 90% Design Package
- Electronic copy of submittal of Permitting Application Packages to Required Agencies.
- Electronic copy of Designer Response to Quality Control Review Comments received from Owner on 60% Design Package

Information and Support from the Owner

- Written review comments on the 90% design package consolidated and listed in the Reviewer portion of the Quality Control Review Comments.

Task 345 - 90% QA/QC Review & Permitting Agency Reviews

Activities

- Submit electronic copy of drawings, specifications, and contract documents to regulatory and code agencies for review and approval.
- Conduct Owner Review.

Deliverables

- 90% Internal QA/QC Review

- 90% Design Review Meeting. Meeting to be four hours long and conducted using Live Meeting. A representative from Black & Veatch, TD&H Engineering and LPW Architects will attend the meeting and other Consultant Team members will participate via Live Meeting.
- Electronic copy of agenda and minutes of Review Meeting
- Designer Response to Quality Control Review Comments received from Owner on 90% Design Package

Task 350 - 100% Detailed Design

Activities

Incorporate 90% review comments and prepare bid ready drawings, specifications, and contract documents.

Deliverables

- Electronic copy of 100% Design Package
- Designer Response to Quality Control Review Comments received from Permitting Agencies on 90% Permitting Review Design Package

Task 360 – Bidding Assistance and Contracting

Activities

- Assist and advise Owner in placing the Invitation to Bid.
- Distribute copies of the Invitation to Bid.
- Reproduce copies of construction contract documents and geotechnical report for distribution to potential bidders.
- Distribute construction contract documents to potential bidders.
- Maintain list of bidders.
- Administer pre-bid conference.
- Respond to bidder questions and requests for clarification.
- Prepare addenda to contract to answer bidder questions. Distribute addenda to potential bidders.
- Attend bid opening.
- Review bids and prepare bid evaluation
- Review bidder qualifications and project experience, contact bidder references, review proposed equipment and material manufacturers, etc.
- Meet with Owner to discuss preliminary evaluation of bids and bidders.
- Tentative award recommendation

Deliverables

- Copies of construction contract documents.

- Electronic copy of addenda
- Bid evaluation
- Recommendation of award

Task 361 – Contingency Task for Detailed Design and Bidding Phases

Activities and deliverables will be provided on an as-needed basis and authorized by the Owner to cover additional services, including those for the detailed design and construction phase services related to the Hazardous Materials Assessment, PLC Conversion, testing of the electrical grounding system, Potholing of buried utilities or other unforeseen engineering activities.

Construction and Commissioning Phase

Task 190 E – Continued Project Management & Controls

Deliverables

- Bi-Weekly Progress Meetings and Schedule Updates via Telephone
- Monthly Invoicing and Budget Status

Task 410 - Construction Admin Support Services

Engineer will perform services during the construction phase of the project. By performing these services, Engineer shall not have authority or responsibility to supervise, direct, or control the Contractor's work or the Contractor's means, methods, techniques, sequences, or procedures of construction. Engineer shall not have authority or responsibility for safety precautions and programs incident to the Contractor's work or for any failure of the Contractor to comply with laws, regulations, rules, ordinances, codes, or orders applicable to the Contractor furnishing and performing the work.

Activities

- Contractor's Schedule ~ Determine if Contractor's schedule is consistent with the construction contract documents with emphasis on milestone dates, construction sequencing, and operation of existing facilities during construction. Engineer's review shall not include an analysis of Contractor's approach, means or methods of construction to perform the work specified in the construction contract documents.
 - Review and comment upon the Contractor's initial construction schedule
 - Review and comment upon updated schedules monthly
- Contractor's Estimates of Monthly Payments ~ Review the Contractor's initial and updated schedule of estimated monthly payments and advise Owner as to acceptability.
- Contractor's Guarantees, Bonds, and Certificates ~ Receive guarantees, bonds, and certificates of inspection, and tests and approvals that are to be assembled by the Contractor. Review for completeness in accordance with the construction contract documents and transmit them to Owner.
- Shop Drawing Review ~ Review drawings and other data submitted by the Contractor as required by the construction contract documents. Engineer's review shall be for general conformity to the construction contract documents and shall not relieve the Contractor of any

of his contractual responsibilities. Such reviews shall not extend to means, methods, techniques, sequences, or procedures of construction or to safety precautions and programs incident thereto.

10. Requests for Information, Change Orders, and Claims ~ The level of effort included for the following services is 400 work hours. Any additional effort related to this task shall be considered as supplemental services.

a. Requests for Information. ~ Interpret construction contract documents when requested by Owner or the Contractor. Requests for clarification or information shall be in writing and copies of Engineer's response shall be distributed to Owner.

b. Change Orders ~ Review Owner or Contractor requests for project changes.

- Review documentation
- Prepare any additional documentation required
- Administer the processing of change orders
- Review applications for extension of construction time.
- Evaluate the cost and scheduling
- Submit recommendations to Owner
- Assist Owner in negotiations with Contractor to obtain a fair price for the work.

c. Claims ~ Act on claims of Owner and the Contractor relating to the acceptability of the work or the interpretation of the requirements of the construction contract documents.

- Performance Testing of Equipment ~ Analyze data from performance testing of equipment by the Contractor or supplier when the construction contract documents require the equipment to be tested after installation. Submit conclusions to Owner.
- Contractor Pay Requests ~ Review and process the Contractor's monthly payment requests, and forward to Owner if appropriate. Engineer's review shall be for the purpose of making a full independent mathematical check of the Contractor's payment request. Engineer is responsible for verifying the quantities of work which are the basis of the payment requests.
- Drawings Conformed to Construction Records ~ Upon completion of the project; revise the construction contract drawings to conform to the construction records. Submit to Owner in Revit software format.
- Conduct Control System Configuration Meetings with UV Disinfection System programmer and the Owner's Configuration Contractor. Prepare agenda and minutes.

Deliverables

- Contractor Schedule Review, Review Estimates of Payments, Shop Drawing Review, RFI Review & Response, Change Order & Claims Review, Drawings Conformed to Construction Records
- Conduct two eight hour long Control System Configuration Meetings with UV Disinfection System programmer and the Owner's Configuration Contractor.
- Electronic copy of agenda and minutes for the Control System Configuration Meetings with UV Disinfection System programmer and the Owner's Configuration Contractor

Task 420 - Field Support Services

Activities

- Preconstruction Conference ~ Conduct the preconstruction conference at a date and time selected by Owner and at a facility provided by Owner. Elements of the conference include:
 - Agenda prepared by Engineer
 - Engineer prepare and distribute minutes
 - Discussion of Contractor's tentative schedules
 - Procedures for transmittal and review of Contractor's submittals
 - Special Inspections Program
 - Processing applications for payment
 - Critical work sequencing
 - Change orders
 - Record documents
 - Contractor's responsibilities for safety and first aid
- Construction Progress Review Meetings ~ Visit the construction site to observe progress of the work, and consult with the Owner and the Contractor. A total of 50 meetings are included.
- Site Visits ~ Project design team personnel with particular areas of responsibilities for the project shall visit the site to observe construction and to confer with Owner and Contractor. Site visits will be as-needed throughout the construction contract.
- Photographic Records ~ Provide, through a subcontract, photographic records of the project.
 - Construction site prior to the start of the construction to assist in defining the original condition of existing physical features, including, but not limited to, pavement, curb and gutter, lawns, shrubs, trees, ditches, fences, sidewalks, buildings, and structures that are located within the limits of construction.
 - Periodic views showing construction progress and elements that will be covered by subsequent construction
-
- Punch List ~ Upon substantial completion, inspect the construction work and prepare a punch list of those items to be completed or corrected before final completion of the project. Submit results of the inspection to Owner and the Contractor. Site inspection, punch list preparation and review of contractor status will be conducted as necessary.
- Final Inspection ~ Upon completion or correction of the items of work on the punch list, conduct a final inspection to determine if the work is completed. Provide written recommendations to Owner concerning final payment, including a list of items, if any, to be completed prior to making such payment. Site inspection and review of contractor status will be conducted as necessary.

Deliverables

Preconstruction Conference, Construction Progress Meetings, Periodic Site Visits, Substantial Completion Inspection, Final Completion Inspection

Task 425 – Structural Tests and Special Inspections

Appendix E presents the Duties, Responsibilities and Limitations of Authority of the Special Inspections Representative.

Activities

- Serve as the Registered Design Professional in Responsible Charge of Construction as defined in IBC 107.3.4.1 for the disciplines of structural engineering, geotechnical engineering, mechanical engineering, electrical engineering, and architectural.
- Prepare the Statement of Special Inspections

Deliverables

- Statement of Special Inspections

Information and Support from the Owner

- Conduct tests and inspections as required by 01450 Structural Tests and Special Inspections.

Task 430 - Onsite Resident Project Representative Services During Construction

Appendix F presents the Duties, Responsibilities and Limitations of Authority of the Resident Project Representative.

Activities

- Provide Resident Project Representative Services

Deliverables

- Site Inspection and Observation, Owner and Contractor Liaison, Engineer Liaison, Outside Agency Liaison, Preconstruction Conference, Construction Progress Meetings, Progress Reporting, Schedule Reviews, Pay Request Processing, Photographic Records, Materials Testing Coordination, Jobsite Files, Daily Log Book, Equipment Testing & Startup, Substantial Completion Inspection, Final Completion Inspection

Task 440 - O&M Manuals

Activities

- Prepare an electronic O&M manual for the UV disinfection system, liquid ammonium sulfate storage and feed system, and the electrical switchgear and procedures that will be added as part of Phase 1. Electronic O&M manual is to be capable of being upgraded by the Owner to include the existing equipment and procedures.
- Prepare the O&M manual content in the format as described below for each unit process:
 - **Overview.** A short, concise description of each unit process identifying the purpose of the equipment within each system. Photographs of major equipment embedded in text.
 - **General Operating Strategy.** A general description of controls. This includes the functional descriptions prepared by PLC/SCADA programmer.

- **Process Flow Schematics.** Simplified figures from the contract drawings and embedded within applicable chapters. These will be located in the first section of the chapter.
- **Key Performance Indicators.** Tabular format of process parameters which the operators either control or monitor the process. Provides target ranges of each of the parameters.
- **Process Troubleshooting.** A list of process alarms and fault conditions showing possible causes and suggested responses. This will be in tabular form.

Deliverables

- Electronic copy of draft and final Part 1 - Operations Plan
- Electronic copy of draft and final Part 2 - Maintenance Plan
- Electronic copy of draft and final Part 3 - Manufacturer's O&M Manuals

Information and Support from the Owner

- Written review comments on the draft documents consolidated and listed in the Reviewer portion of the Quality Control Review Comments.

Task 450 - Start-up Assistance, Training, & Post-Construction Activity

Activities

- Pre- & Post-start-up Training
 - UV 101 and applications training (1 trip, multiple sessions over 1 week period) – goal is to provide additional background training on UV disinfection and role of UV system in disinfection strategy for Great Falls WTP.
 - Participation in Xylem provided Operations and Maintenance training (includes total of 6 sessions for 8 hrs. each: 3 maintenance and 3 operation sessions) – goal is to provide B&V presence during the training sessions provided by Xylem observe and provide assistance
- Start-up Assistance
- Performance Testing
 - Review/approval of Xylem prepared protocols
 - On-site supervision of testing by Xylem personnel (1 week on-site)
 - Analysis of test data
 - Review/approval of performance test report prepared by Xylem
- Operational Consultation

Deliverables

- UV 101 Applications Training
- Agenda and handouts for UV 101 Applications Training

Task 451 – Contingency Task for Construction and Commissioning Phases

Activities and deliverables will be provided on an as-needed basis and authorized by the Owner.

Schedule

The schedule for the Detailed Design and Bidding Phases is shown in the following graphic. The schedule is based on the following: 1) it is independent of the schedule for completing the services associated with replacing the NW Energy Substation and coordinating with NW Energy, 2) it does not regard the time NW Energy needs to complete their services, 3) it is based the revised BIM Workflow Model that the Engineer will use for executing the services for detailed design. The schedule may or may not allow for completion of the services related to the NW Energy Substation. The approach is to continue to attempt to advance the design of the replacement of the NW Energy Substation. The Owner will decide at the time of bidding the construction of the Phase 1 as to whether the Alternate Bid Item No. 1 – Replacement of the NW Energy Substation will be included in the Phase 1.

The Opinion of Probable Schedule for the construction of Phase 1 is 24 months from the notice to proceed for construction.

Fees

The fees for the Detailed Design, Bidding, Construction and Commission Phase services are shown in the following table. The fees assume: 1) one construction contract, 2) preparation of one bid package, 3) a 24 month construction duration, 3) the conceptual design of Phase 1 shown in the Task 282C Phase 1 Drawings contained in Appendix A, and 4) the information and schematics on existing SCADA System shown in Appendix D.

Appendix A - Task 282 C Phase1 Drawings

Appendix B – Preliminary List of Drawings

List of Drawings for Phase 1 of the Water Treatment Facility Upgrades

Discipline	Sub-Discipline	Sheet No.	Drawing No.	Title
General Drawings				
			GL-1	Sheet List
			GL-2	Legend and Abbreviations
Civil Site Development				
	General Civil Site Plans			
			GC-1	Overall Site, Access & Staging Plan
	Demolition			
			SR-1	West Site Demolition Plan
			SR-2	West Site Demolition Plan – Base Bid + Bid Alternate No. 1
			SR-3	Central Site Demolition Plan
			SR-4	East Site Demolition Plan
			SR-5	East Site Demolition Plan – Base Bid + Bid Alternate No. 2
	Site Grading Plans			
			TG-1	West Site Grading Plan
			TG-2	West Site Grading Plan – Base Bid + Bid Alternate No. 1
			TG-3	Central Site Grading Plan
			TG-4	East Site Grading Plan
			TG-5	East Site Grading Plan – Base Bid + Bid Alternate No. 2
	Site Piping Plans			
			SD-1	West Site Piping Plan
			SD-2	Central Site Piping Plan
			SD-3	East Site Piping Plan – Bid Alternate No. 2
	Landscaping			
			LA-1	West Landscape Plan
			LA-2	West Landscape Plan – Base Bid + Bid Alternate No. 1
			LA-3	Central Landscape Plan
			LA -4	East Landscape Plan

Discipline	Sub-Discipline	Sheet No.	Drawing No.	Title
			LA-5	East Landscape Plan – Base Bid + Bid Alternate No. 2
	Yard Structures			
			SY-1	Expanded Yard Piping Plans
			SY-2	Expanded Yard Piping Plans
			SY-3	Electrical Room Addition Foundation Drain Plan
			SY-4	Chemical Feed and UV Disinfection Building Foundation Drain Plan
			SY-5	Yard Piping Profiles
			SY-6	Yard Structures
			SY-7	Civil Details 1
			SY-8	Civil Details 2
			SY-9	Civil Details 3
			SY-10	Electrical Room Addition Foundation Drain Pump Station Plan & Details
			SY-11	Chemical Feed and UV Disinfection Building Foundation Drain Pump Station Plan & Details
Architectural				
	Administration Building Addition			
			AA-1	Code Plan / Overall Floor Plan
			AA-2	Main Level Floor Plan
			AA-3	Plan Details
			AA-4	Roof Plan / Roof Details
			AA-5	Building Sections
			AA-6	Building Sections
			AA-7	Wall Sections
			AA-8	Wall Sections
			AA-9	Section Details
			AA-10	Exterior Elevations
			AA-11	Exterior Elevations
			AA-12	Interior Elevations
			AA-13	Door and Window Schedules
			AA-14	Door and Window Details

Discipline	Sub-Discipline	Sheet No.	Drawing No.	Title
			AA-15	Millwork Details
			AA-16	Reflected Ceiling Plan
			AA-17	Finish Floor Plan / Schedule
Chemical Feed and UV Disinfection Building				
			AC-1	Code Plan
			AC-2	Lower Level Floor Plan / Details
			AC-3	Main Level Floor Plan / Details
			AC-4	Roof Plan / Roof Details
			AC-5	Building Sections
			AC-6	Wall Sections
			AC-7	Section Details
			AC-8	Exterior Elevations
			AC-9	Door and Window Schedules / Details
			AC-10	Exterior Elevations
			AC-11	Exterior Elevations
			AC-12	Door and Window Schedules / Details
			AC-13	Finish Floor Plan / Schedule
Pump Station Modifications				
			AP-1	Code Plan / Overall Floor Plan
			AP-2	Lower Level Floor Plan / Main Level Floor Plan
			AP-3	Roof Plan / Roof Details
			AP-4	Building Sections
			AP-5	Wall Sections
			AP-6	Section Details
			AP-7	Exterior Elevations
			AP-8	Exterior Elevations
			AP-9	Door and Window Schedules / Details
			AP-10	Finish Floor Plans

Discipline	Sub-Discipline		Sheet No.	Drawing No.	Title
	Surge Tank				
				AS-1	Floor Plan
				AS-2	Building Sections
				AS-3	Wall Sections
				AS-4	Roof Plan / Details
Civil					
	Chemical Feed and UV Disinfection Building				
				CC-1	Upper Level Floor Plan
				CC-2	Lower Level Floor Plan
				CC-3	Sections
				CC-4	Sections and Details
	Head House Modifications				
				CH-1	Chlorine Room Plan
				CH-2	Chlorine Storage Room Plan
	Surge Tank				
				CS-1	Surge Tank Civil Floor Plan
				CS-2	Surge Tank Civil Sections
				CS-3	Surge Tank Civil Sections
				CS-4	Surge Tank Civil Details
				CS-5	Surge Tank Civil Details
	General				
				GC-1	
				GC-2	
Structural Drawings					
	Administration Building Addition				
				SA-1	General Structural Specs
				SA-2	General Structural Specs

Discipline	Sub-Discipline	Sheet No.	Drawing No.	Title
			SA-3	Foundation Plan
			SA-4	Main Floor Plan
			SA-5	Roof Plan
			SA-6	Section Views
			SA-7	Section Views
			SA-8	Section Views
			SA-9	Section Views
			SA-10	Detail Views
			SA-11	Detail Views
			SA-12	Detail Views
			SA-13	Detail Views
			SA-14	Detail Views
	Chemical Feed and UV Disinfection Building			
			SC-1	General Structural Specs
			SC-2	General Structural Specs
			SC-3	Foundation Plan
			SC-4	Lower Level Plan
			SC-5	Main Floor Plan
			SC-6	Roof Plan
			SC-7	Section Views
			SC-8	Section Views
			SC-9	Section Views
			SC-10	Section Views
			SC-11	Detail Views
			SC-12	Detail Views
			SC-13	Detail Views
			SC-14	Detail Views
			SC-15	Detail Views
	Head House Modifications			

Discipline	Sub-Discipline	Sheet No.	Drawing No.	Title
			SH-1	General Structural Specs
			SH-2	Main Level Demolition/Modification Plan
			SH-3	Level 2 Demolition/Modification Plan
			SH-4	Detail Views
			SH-5	Detail Views
	Pump Station Modifications			
			SP-1	General Structural Specs
			SP-2	General Structural Specs
			SP-3	Foundation Plan
			SP-4	Basement Level Plan
			SP-5	Main Level Plan
			SP-6	Roof Plan
			SP-7	Section Views
			SP-8	Section Views
			SP-9	Section Views
			SP-20	Section Views
			SP-11	Detail Views
			SP-12	Detail Views
			SP-13	Detail Views
			SP-14	Detail Views
			SP-15	Detail Views
			SP-15	Level 1 Demolition/Modifications Plan
			SP-16	Detail Demolition/Modification Views
	Surge Tank			
			SS-1	General Structural Specs
			SS-2	Foundation Plan
			SS-3	Floor Plan
			SS-4	Section Views
			SS-5	Section Views

Discipline	Sub-Discipline	Sheet No.	Drawing No.	Title
			SS-6	Detail Views
			SS-7	Detail Views
NW Energy Metering and Service Disconnect Building				
			SM -1	General Structural Specs
			SM-2	Foundation Plan
			SM-3	Floor Plan
	General			
			GS-1	Overall Project General Structural Specs
HVAC Drawings				
Administration Building Addition				
			HA-1	Administration Building Addition Floor Plan
			HA-2	Filter Building Locker Room Addition Floor Plan
			HA-3	Sections
Chemical Feed and UV Disinfection Building				
			HC-1	Administration Building Addition Floor Plan
			HC-2	Filter Building Locker Room Addition Floor Plan
			HC-3	Sections
Pump Station Modifications				
			HP-1	Floor Plan
			HP-2	Roof Plan
	General			
			GH-1	Schedules
			GH-2	Sequence of Operation and Details
Plumbing Drawings				
Administration Building Addition				
			PA-1	Floor Plan – Water Supply
			PA-2	Floor Plan - Drainage
			PA-3	Piping Isometric Diagrams

Discipline	Sub-Discipline	Sheet No.	Drawing No.	Title
	Chemical Feed and UV Disinfection Building			
			PC-1	Floor Plan – Water Supply
			PC-2	Floor Plan - Drainage
			PC-3	Piping Isometric Diagrams
	Head House Modifications			
			PH-1	Lower Level Floor Plan
	General			
			GP-1	Schedules
			GP-2	Details
Instrumentation & Control Drawings				
			I-1	P&ID Legend & Abbreviations
			I-2	P&ID Legend & Abbreviations
			I-3	P&ID UV Disinfection Systems
			I-4	P&ID Liquid Ammonia Storage System
			I-5	P&ID Liquid Ammonia Feed System
			I-6	Control System Block Diagram
			I-7	Instrument Installation Details
Electrical Drawings				
	Administration Building Addition			
			EA-1	Administration Building Power Plan - Alternate Bid Item No. 2
			EA-2	Administration Building Lighting Plan - Alternate Bid Item No. 2
			EA-3	Admin Bldg One-line diagrams - Alternate Bid Item No. 2 Misc starters, power panel, UPS system
			EA-4	Admin Bldg One-line diagrams - Alternate Bid Item No. 2. FACP, Comm, Telephone, Security
			EA-5	Admin Bldg one-lines & Schematics - Alternate Bid Item No. 2 HVAC, Entrance Gate
			EA-6	Admin Bldg Schedules and Details - Alternate Bid Item No. 2 Panelboard and Lighting Schedules

Discipline	Sub-Discipline	Sheet No.	Drawing No.	Title
	Chemical Feed and UV Disinfection Building			
			EC-1	Chemical Feed & UV Disinfection Building Power Plan Upper Level
			EC-2	Chemical Feed & UV Disinfection Building Power Plan Lower Level
			EC-3	Chemical Feed & UV Disinfection Building Lighting Plan Upper Level
			EC-4	Chemical Feed & UV Disinfection Building Lighting Plan Lower Level
			EC-5	Chemical Feed & UV Disinfection Building One-line diagrams LV Switchgear 1A & 1B and Elevation
			EC-6	Chemical Feed & UV Disinfection Building One-line diagrams MCC - 1 & 2 and Elevations
			EC-7	Chemical Feed & UV Disinfection Building One-line diagrams UV Disinfection and Chemical Equipment One-line diagrams
			EC-8	Chemical Feed & UV Disinfection Building One-line diagrams LAS Chemical Equipment One-line diagrams
			EC-9	Chemical Feed & UV Building One-line diagrams FACP, Comm, Telephone, Security, and Vent Failure Alarm Panels
			EC-10	Chemical Feed & UV Disinfection Building One-line diagrams PLC one-line diagram and Valve Actuators
			EC-11	Chemical Feed & UV Disinfection Building One-lines & Schematics HVAC
			EC-12	LV Genset One-line Diagrams Gen Cntl Panel and power panel
			EC-13	Chemical Feed & UV Disinfection Building Schedules Panelboard and Lighting Schedules
	Head House Modifications			
			EH-1	Head House Power Plans Levels 1 and 2
			EH-2	Head House Power Plans Basement Floor - Alternate Bid Item No. 2
			EH-3	Head House One-Line Diagrams Demo and Modification
			EH-4	Locker Room - 1916 Filter Area
			EH-5	Schedules Panelboards
	Pump Station Modifications			

Discipline	Sub-Discipline	Sheet No.	Drawing No.	Title
			EP-1	Existing Pump Station Demolition Power Plan
			EP-2	MV Switchgear Demolition One-line Diagram
			EP-3	LV Distribution Demolition One-line Diagram
			EP-4	Pump Station Power Plan Level 1
			EP-5	Pump Station Electrical Room Addition Power Plan Main Level
			EP-6	Pump Station Electrical Room Addition Power Plan Main Level Alternate Bid Item No. 2
			EP-7	Pump Station Electrical Room Addition Lighting Plan Main Level
			EP-8	Pump Station Electrical Room Addition Lighting Plan Main Level Alternate Bid Item No. 2
			EP-9	Pump Station Electrical Room Addition Power Plan Basement Level (Floor & Wall Penetrations)
			EP-10	Pump Station Electrical Room Addition Lighting Plan Basement Level
			EP-11	5 kV Main Switchgear One-line Diagram PDFD and Protective Relaying
			EP-12	5 kV Main Switchgear One-line Diagram - continued PDFD and Protective Relaying
			EP-13	5 kV Main Switchgear One-line Diagram - continued PDFD and Protective Relaying
			EP-14	5 kV Main Switchgear One-line Diagram Power and Control Connections
			EP-15	Pump Station One-line Diagrams 125Vdc Switchgear Control Power Panel
			EP-16	Pump Station MV Breaker Schematics Main, Tie, and Feeder
			EP-17	Pump Station One-line Diagram LV Switchgear 2 One-line Diagram and Elevation
			EP-18	Irrigation Pump One-line Diagram and Schematic MCC-IRR
			EP-19	Pump Station One-line Diagrams MCC-3 and 4 One-lines and Elevations
			EP-20	Pump Station One-line Diagrams Panel P1
			EP-21	Pump Station One-line Diagrams Panel P2
			EP-22	Pump Station One-line Diagrams Panel P3
			EP-23	Pump Station One-Lines HVAC and misc starters
			EP-24	Pump Stations One-lines FACP and Telephone

Discipline	Sub-Discipline	Sheet No.	Drawing No.	Title
			EP-25	Pump Stations One-lines Security and Communications
			EP-26	Pump Station PLC One-line Modifications
			EP-27	Pump Station PLC One-line Modifications
			EP-28	Pump Station PLC One-line Modifications
			EP-29	Pump Station Schematics HVAC and misc starters
			EP-30	Pump Station Schedules Panelboards
			EP-31	Pump Station Schedules Panelboard and Lighting Schedules
	Surge Tank			
			ES-1	Surge Tank Plan
			ES-2	Miscellaneous Details
	NW Energy Substation			
			EN-1	NWE Substation One-line Diagram Modifications
			EN-2	NWE Substation One-line Diagram Modifications – Alternate Bid Item No. 1
			EN-3	NW Energy Metering & Service Disconnect Building Plan - Alternate Bid Item No. 1 Equipment arrangement and 5kV Utility Switchgear Elevation
			EN-4	NWE Switchgear One-line Diagram - Alternate Bid Item No. 1 PDFD & Protective Relaying
			EN-5	NWE Switchgear One-line Diagram & Schematics- Alternate Bid Item No. 1 Power and Control Connections/Typ CB Schematic
			EN-6	One-line Diagrams - Alternate Bid Item No. 1 FACP, 480V PP, HVAC, DC Panel,
			EN-7	Schematics and Details - Alternate Bid Item No. 1
	General			
			GE-1	Legend and Abbreviations
			GE-2	Site Plan - East
			GE-3	Site Plan - East – Alternate Bid Item No. 2

Discipline	Sub-Discipline	Sheet No.	Drawing No.	Title
			GE-4	Site Plan - Central
			GE-5	Site Plan - West
			GE-6	Site Plan - West – Alternate Bid Item No. 1
			GE-7	Duct Bank Sections and Duct Bank Schedule
			GE-8	Expanded Site Plan Existing NWE Substation Plan
			GE-9	Expanded Site Plan New NWE Substation Plan
			GE-10	Expanded Site Plans Carbon Storage Building
			GE-11	Expanded Site Plans – Alternate Bid Item No. 2 Administration Building Site Power and Lighting Plan
			GE-12	Site Details LV Generator Plan and Load Center Building Plan
			GE-13	Site Details Manholes, handholes, grounding transformer pads, misc structures
			GE-14	Site Details Miscellaneous Area (Backwash Water Trt XFMR mods)
			GE-15	WTP Power Distribution Functional Diagram 5kV Main Switchgear & MV Starter Line-ups
			GE-16	WTP Power Distribution Functional Diagram – Alternate Bid Item No. 1 5kV Main Switchgear & MV Starter Line-ups

Appendix C – Preliminary Table of Contents for Project Manual

Table of Contents for Project Manual for Phase 1 of the Water Treatment Facility Upgrades

Subject	Pages
BIDDING REQUIREMENTS	
00020 Invitation to Bid	1 :
00100 Instructions to Bidders	1 :
BIDDING FORMS	
00400 Bid Form	1 :
00430 Bid Bond – Penal Sum Form	1 : 2
00435 Bid Bond – Damages Form	1 : 2
00440 List of Subcontractors	1 :
00450 Equipment Questionnaire	1 :
00452 Instrumentation and Control System Supplier Questionnaire	1 :
OWNER’S FORMS	
00482 Certification of Nonsegregated Facilities	1
XXXXX Certification of Compliance with Insurance Requirements	1
CONTRACTING FORMS	
00500 Agreement (New Owner format with Exhibits)	1 :
00510 Notice of Award	1
00550 Notice to Proceed	1
00560 Certificate of Liability Insurance(After Bid/Before Award)	1
00562 Certificate of Property Insurance(After Bid/Before Award)	1
00570 Assignment of Procurement Contract	1

00575	Surety's Agreement to Assignment	1
00610	Performance Bond	1 : 2
00615	Payment Bond	1 : 2
00620	Application for Payment	1 : 3
00625	Certificate of Substantial Completion	1

CONDITIONS OF THE CONTRACT

00700	Standard General Conditions of the Construction Contract	1 : 42
00800	Supplementary Conditions	1 :

Attachments

00800A	Duties, Responsibilities, and Limitations of Authority of the Resident Project Representative as Set Forth in the Owner/Engineer Agreement	1 :
--------	--	-----

00800B	Duties, Responsibilities, and Limitations of Authority of the Special Inspections Representative as Set Forth in the Owner/Engineer Agreement	
--------	---	--

00800C	American Iron and Steel (AIS) Requirements	
--------	--	--

00800D	Employment Requirements	
	Wage Rate Determination (Suggest include all MT Categories and require higher scale for duplicate disciplines)	

Labor Standards Provisions

Notice to Labor Unions or Other Organizations of Workers Certification of Nonsegregated Facilities Standard Federal Equal Employment Opportunity Construction Contract Specifications	EEO-1: EEO-2
Notice of Requirements for Affirmative Action to Ensure Equal Employment Opportunity	RAA-1 : RAA-2
EPA - Procurement Under Assistance Agreements (40 CFR Part 33)	1 : 18

ADMINISTRATIVE FORMS

00900	Funding Agency Special Provisions for MT Public Facility Projects	1:32
00940	Work Change Directive Form	1
00941	Change Order Form	1 : 2
00942	Field Order Form	1

SPECIFICATIONS

DIVISION 1 – GENERAL REQUIREMENTS

01015	Project Requirements	1 :
01018	Drawings	1 :
01070	Abbreviations of Terms and Organizations	1 :
01300	Submittals Procedures	1 :
01310	Construction Progress Schedule	1 :
01320	Construction Progress Documentation	1 :

01380	Construction Photographs	1 :
01400	Quality Control	1 :
01450	Structural Tests and Special Inspections	1 :
01500	Temporary Facilities	1 :
01610	General Equipment Stipulations	1 :
01611	Meteorological and Seismic Design Criteria	1 :
01612	Product Delivery Requirements	1 :
01614	Product Storage and Handling Requirements	1 :
01615	Equipment and Valve Identification	1 :
01620	Equipment Schedule	1 :
01630	Pipeline Schedule	1 :
01650	Startup Requirements	1 :
01820	Demonstration and Training	1 :

DIVISION 2 – SITEWORK

02015	Geotechnical Report	1 :
02110	Geotextiles	1 :
02112	Removal of Existing Pavement, Concrete Curb, Sidewalk, Driveway and/or Structures	1 :
02113	Adjusting Existing Manholes, Lampoles, Inlets, Water Valve Boxes, Water Services and Fire Hydrants to Grade	1 :
02114	Relocating or Removing Utility Poles, Street Signs and Mailboxes	1 :
02150	Clearing and Grubbing	1 :
02221	Trench Excavation and Backfill for Pipelines and Appurtenant Structures	1 :
02203	Site Grading, Excavation and Embankment	1 :
02225	Flowable Fill	1 :
02234	Sub Base Course	1 :
02235	Crushed Base Course	1 :
02372	Drilled Concrete Piers and Shafts (Rodney?)	1 :
02502	Asphalt Prime and/or Tack Coat	1 :
02510	Asphalt Concrete Pavement	1 :
02515	Portland Cement Concrete Pavement	1 :
02528	Concrete Curb and Gutter	1 :
02529	Concrete Sidewalks, Driveways, Approaches, Curb Turn Fillets, Valley Gutters and Miscellaneous New Concrete Construction	1 :
02581	Pavement Markings and Markers (Pre-Formed Plastic, Paints and Enamels)	1 :
02661	Foundation Drains	
02662	Underground Piping	1 :
02671	Underground Gate Valves	1 :
02673	Underground Butterfly Valves	1 :
02720	Storm Drain Systems	1 :
02725	Drainage Culverts	1 :
02801	Chain Link Fencing	1 :
02910	Seedings	
02920	Hydraulic Seeding	1 :
02930	Irrigation Systems	1 :
02940	Landscape Plantings	1 :

DIVISION 3 – CONCRETE

03100	Concrete Forming	1 :
03200	Concrete Reinforcing	1 :
03250	Concrete Joints and Accessories	1 :
03300	Cast-in-Place Concrete	1 :
03301	Miscellaneous Cast-in-Place Concrete	1 :
03315	Lightweight Structural Concrete	1 :
03350	Concrete Placing, Finishing, and Curing	1 :
03430	Precast Structural Concrete	1 :
03600	Grouting	1 :
03930	Concrete Crack Repair	1 :

DIVISION 4 – MASONRY

04200	Masonry	1 :
04220	Masonry Reinforcing	

DIVISION 5 – METALS

05300	Steel Decking	1 :
05440	Cold Formed Steel Trusses	1 :
05500	Metal Fabrications	1 :
05520	Handrailing, Guardrailing, and Ladders	1 :
05530	Grating	1 :
05550	Anchorage In Concrete and Masonry	1 :
05990	Structural and Miscellaneous Metals	1 :

DIVISION 6 – WOOD AND PLASTICS

06090	Carpentry	1 :
06200	Shop Fabricated Wood Trusses	1 :

DIVISION 7 – THERMAL AND MOISTURE PROTECTION

07160	Dampproofing	1 :
		1 :
		1 :

		1 :
07532	EPDM Roofing, Fully Adhered	1 :
07600	Flashing and Sheet Metal	1 :
07900	Joint Sealants	1 :
DIVISION 8 – DOORS AND WINDOWS		
08110	Steel Doors and Frames	1 :
08305	Floor Access Doors and Hatches	1 :
08330	Overhead Coiling Steel and Fire Doors	1 :
08410	Aluminum Entrances and Assemblies	1 :
08520	Aluminum Windows	1 :
08700	Hardware	1 :
08800	Glass Glazing	1 :
DIVISION 9 – FINISHES		
09250	Gypsum Board	1 :
09310	Ceramic Tiling	1 :
09510	Acoustical Panel Ceilings	1 :
09660	Resilient Flooring	1 :
09920	Painting	1 :
09940	Protective Coatings	1 :
DIVISION 10 – SPECIALTIES		
10200	Louvers and Vents	1 :
10500	Metal Lockers	1 :
10800	Toilet Accessories	1 :
DIVISION 11 – EQUIPMENT		
11060	Equipment Installation	1 :
11115	Portable Chemical Pumps	1 :
11185	Submersible Sump and Sewage Pumps	1 :
11720	UV Cleaning Storage and Feed System	
11725	Gas Chemical Feed Systems	1 :
11727	Liquid Chemical Feed Systems	1 :

11910 Engine Generators 1 :

DIVISION 12 – FURNISHINGS – Not Used

DIVISION 13 – SPECIAL CONSTRUCTION

13140 Pre-fabricated Electrical Building 1 :
13190 Fiberglass Reinforced Plastic Chemical Storage Tanks 1 :
13199 Chemical Storage Tank Installation 1 :
13500 Instrumentation and Control System 1 :
13530 Programmable Logic Controllers 1 :
13540 Multiple Address Radio Equipment 1 :
13550 Software Control Block Descriptions 1 :
13561 Panel Mounted Instruments 1 :
13562 Flow Instruments 1 :
13563 Pressure and Level Instruments 1 :
13564 Process Analytical Instruments 1 :
13565 Miscellaneous Instruments 1 :
13570 Panels, Consoles, and Appurtenances 1 :
13590 Ethernet Networks 1 :
13591 Network Cabling 1 :
13930 Fire-Suppression Sprinkler Systems 1 :

DIVISION 14 – CONVEYING SYSTEMS

14621 Monorail Chain Hoists 1 :
14630 Bridge Cranes 1 :
14641 Portable Gantry Cranes 1 :
14650 Jib Cranes 1 :

DIVISION 15 – MECHANICAL

15010 Valve Installation 1 :
15020 Miscellaneous Piping and Accessories Installation 1 :
15050 Basic Mechanical Building Systems Materials and Methods 1 :
15060 Miscellaneous Piping and Pipe Accessories 1 :
15061 Ductile Iron Pipe 1 :

15062	Steel Pipe	1 :
15064	Stainless Steel Pipe, Tubing, and Accessories	1 :
15065	Miscellaneous Steel Pipe, Tubing, and Accessories	1 :
15067	Miscellaneous Plastic Pipe, Tubing, and Accessories	1 :
15069	Cast Iron Soil Pipe and Accessories	1 :
15070	Copper Tubing and Accessories	1 :
15091	Miscellaneous Ball Valves	1 :
15093	Check Valves	1 :
15094	Backflow Preventers	1 :
15096	Globe Valves	
15098	Plug Valves	1 :
15099	Pressure Reducing Valves	1 :
15100	Miscellaneous Valves	1 :
15101	AWWA Butterfly Valves	1 :
15104	Resilient-Seated Gate Valves	1 :
15108	Air Valves	1 :
15140	Pipe Supports	1 :
15150	Water Meters	1 :
15160	Flow Tubes and Venturi Tubes	1 :
15180	Valve and Gate Actuators	1 :
15250	Mechanical Insulation	1 :
15400	Plumbing	1 :
15550	Heating Systems Equipment	1 :
15650	Refrigeration Systems	1 :
15755	Industrial Heat Exchangers	1 :
15880	Air Distribution Systems	1 :
15955	Building System Controls	1 :
15990	Testing, Adjusting, and Balancing	1 :

DIVISION 16 – ELECTRICAL

16050	Electrical	1 :
16100	Electrical Equipment Installation	1 :
16220	General Purpose Induction Motors	1 :
16310	Secondary Integral Unit Substations	1 :

16345	Medium-Voltage Metal-clad Switchgear	1 :
16346	Low-Voltage Switchgear	1 :
16480	600 Volt Class Motor Control Centers	1 :
16670	Lightning Protection for Structures	1 :
16721	Fire Detection and Alarm System	1 :
16725	Electronic Security Systems	1 :
16xxx	Low Resistance Grounding System	

FIGURES

Number	Title	Following Page
1-01300	Submittal Identification & Contractor's Approval Statement	01300-
2-01300	Submittal Identification & Contractor's Approval Statement	01300-
1-01612	Export Shipment Packing Instructions	01612-
2-01612	Marking Instructions	01612-
1-09940	Coating System Data Sheet	09940-
2-09940	Coating System Data Sheet	09940-
1-13500	Instrument Calibration Report	13500-
1-15062(A)	Steel Pipe Fittings	15062-
1-15062(B)	Dimensions for Steel Pipe Fittings	15062-
2-15062	Installation Detail - Potential Test Lead Station	15062-
3-15062(A)	Field-Welded Lap Joint Detail – Double Welded Bell	15062-
3-15062(B)	Field-Welded Lap Joint Detail – Single Welded Bell	15062-
1-15140(A)	Hangers and Supports	15140-
1-15140(B)	Hangers and Supports	15140-

1-16050	600 Volt, Single Conductor Lighting Cable (THHN-THWN)	16050-
2-16050	600 Volt, Single Conductor Lighting/Power Cable (XHHW)	16050-
3-16050	600 Volt, Single Conductor Power Cable (THHN- THWN)	16050-
4-16050	600 Volt, Single Pair Shielded Instrument Cable	16050-
5-16050	600 Volt, Single Triad Shielded Instrument Cable	16050-
6-16050	600 Volt, Multiple Pair and/or Triad Shielded Instrument Cable	16050-
7-16050	600 Volt, Multiconductor 14 AWG Control Cable (THHN-THWN)	16050-
8-16050	600 Volt, Multiconductor 12 AWG Control Cable (THHN-THWN)	16050-
9-16050	8000 Volt, Single Conductor Power Cable (EPR)	16050-
10-16050	15,000 Volt, Single Conductor Power Cable (EPR)	16050-
11-16050	600 Volt, 3 Conductor with Ground Power Tray Cable	16050-
12-16050	600 Volt, Single Conductor Power Tray Cable	16050-
13-16050	600 Volt, Single Conductor Power Cable (RHH-RHW-USE)	16050-
14-16050	600 Volt, Type MC Metal Clad Lighting Cable	16050-
15-16050	2000 Volt, 3 Conductor Adjustable Frequency Drive Cable	16050-
16-16050	Cable Test Data Form	16050-

Appendix D – Information and Schematics on Existing SCADA System

IAC has as-built drawings for the following:

1. Backwash Clarifier: 90-30 control system, IC693CPU374 w/ 10/100 ENet.
2. Head House: 90-30 control system, IC693CPU366 w/ Profibus Master, add-on ENet card.
3. Filter Building: 90-30 control system, IC693CPU366 w/10/100 ENet. A full set of drawings was not produced for this project as per Owner's direction. Drawings are mainly for panel layouts, I/O module layouts, and typical connection details to field devices.

It is not known what drafted documentation is available for all of the remote terminal units (RTUs). The only RTUs IAC was involved with are at the Gore Hill Tank and The Gore Hill Pump Station. RTU as-builts will probably be only what the Owner has on file.

The documentation for the wireless communications networks shows that a mix of frequencies and protocols are being used.


1. 14.375 GHz full duplex between a MDS Master Station at the Filter Building and a repeater at Hill 57. Modbus protocol.
2. 14.375 GHz full duplex between the repeater and five RTUs that use MDS 9710b radios. Modbus protocol.
3. 902-928 MHz FHSS between remote Modbus masters and groups of Modbus slaves using MDS9810b radios. Communications between the remote Modbus masters and the Hill 57 repeaters is always at 14.375 GHz.
4. All GE VersaMax PLCs communicate with the Hill 57 repeater at 14.375 GHz, Modbus protocol.
5. Modbus TCP is not used anywhere.
6. The filter building control room 90-30 PLC and the Chlorine building VersaMax PLC communicate with the HMI using 10BaseT over copper.
7. The SCADA servers and client PCs communicate using 100BaseT over copper.
8. The backbone between the Filter Building and the Pump Station is over 1 GHz fiber.

There are a few other variations, but the takeaway from this information is that the WTP communications architecture is already built for performance where possible. Slower communications is used where the control or the communications equipment does not support higher bandwidth.

City of Great Falls Water System SCADA Infrastructure					
Wired Network Topology					
Dwg 1	WTP Network Overview				
	Location	Comm	Location		
	Filter Building	T1	City of Great Falls WAN		
	Filter Building	Dual 1000BaseSX	Pump Station		
	Pump Station	10BaseT	Backwash Clarifier		
Dwg 2	Filter Building (FB)				
	Equipment	Comm	Location or Equipment	Comm	Location or Equipment
	FB SCADA Router	1000BaseSX	Pump Station Building		
		10BaseT	FB Control Room 90-30 PLC	RS232 Modbus	MDS Master Transceiver
		10BaseT	FB Chlorine Room VersaMax Micro PLC		
		100BaseTX	Multilin ML2400 Managed Switch	100BaseFX	Head House Multilin ML600 Switch
		100BaseTX	Historian Server 1	100BaseTX	Historian Server 2
			Historian Server 1	100BaseTX	FB COGF Router
		1000BaseTX	FB COGF Router		
	Equipment	Comm	Location or Equipment	Comm	Location or Equipment
	FB COGF Router	1000BaseTX	FB SCADA Router		
		1000BaseSX	Pump Station Building		
		100BaseTX	Historian Server 2		
		100BaseTX	Control Server 2		
		100BaseTX	CCTV DVR		
		100BaseTX	Control Room Workstation 1		
		100BaseTX	Lab Workstation		
		100BaseTX	Control Room Information Workstation		
		100BaseTX	Cisco 1700 Series Router	T1	City of Great Falls WAN
Dwg 3	Pump Station Building				
	Equipment	Comm	Location or Equipment		
	PS COGF SCADA Router	10BaseT	Backwash Clarifier		
		1000BaseSX	Filter Building		
		1000BaseTX	PS COGF Router		
		10BaseT	PS Control Room 90-30 PLC		
	Equipment	Comm	Location or Equipment		
	PS COGF Router	1000Base TX	PS COGF SCADA Router		
		1000BaseSX	Filter Building		
		100BaseTX	Office Workstation		
		100BaseTX	Office Maintenance Workstation		
		100BaseTX	Maintenance Management Server		
		100BaseTX	Engineering Workstation		
		100BaseTX	IBM Printer		
		100BaseTX	Kyocera Printer		
Dwg 4	Backwash Clarifier Building				
	Equipment	Comm	Location or Equipment		
	Backwash Clarifier Versamax PLC	10BaseT	Pump Station Building		
Dwg 5	Head House				
	Equipment	Comm	Location or Equipment		
	Multilin ML600 Switch	10BaseT	Headhouse 90-30 PLC		
		100BaseTX	QuickPanel OIT		
		100BaseFX	Filter Building Control Room		


City of Great Falls Water System SCADA Infrastructure											
Wireless Network Topology											
Dwg 6 Wireless SCADA											
	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC				
	Filter Building SCADA Master 90-30 PLC	RS232 Modbus	Master Station MDS 9790B Radio	14.375 GHz	Hill 57 Booster Station MDS 3131 Repeater Radio	14.375 GHz	Boston Heights Standpipe MDS 9710B Radio				
						14.375 GHz	Malmstrom AFB MDS 9710B Radio				
						14.375 GHz	Gore Hill Booster Station MDS 9710B Radio				
						14.375 GHz	Fire Station 1 MDS 9710B Radio				
						14.375 GHz	33rd St. Booster Station MDS 9710B Radio				
Dwg 7 Hill 57 Booster											
	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC		
	Hill 57 Booster Station MDS 3131 Repeater Radio	RS232 Modbus	33rd St. Booster Station 90-30 PLC	RS232 Modbus	Hill 57 Modbus Master MDS 9810b FHSS Radio	900 Mhz	Skyline Tank MDS 9810b FHSS Radio	RS232 Modbus	Skyline Tank 90-30 PLC		
						900 Mhz	Riverview Booster MDS 9810b FHSS Radio	RS232 Modbus	Ella Tank Versamax Micro PLC		
Dwg 8 Gore Hill Booster											
	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC
	Hill 57 Booster Station MDS Repeater Radio	952TX/928RX MHz	Gore Hill Booster MDS 9710b Radio	RS232	Gore Hill Booster Station 90-30 PLC	RS232/CCM Protocol	Gore Hill Booster MDS 9810b FHSS Radio	900 Mhz FHSS	Gore Hill Tank MDS 9810b FHSS Radio	RS232/CCM Protocol	Gore Hill Tank 90-30 PLC
Dwg 9 33rd Street Booster											
	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC
	Hill 57 Booster Station MDS Repeater Radio	952TX/928RX MHz	33rd Street Booster MDS 9710b Radio	RS232	33rd St. Booster 90-30 PLC	RS232/CCM Protocol	33rd Street Booster MDS 9810b FHSS Radio	900 Mhz	Ella Tank MDS 9810b FHSS Radio	RS232/CCM Protocol	Ella Tank 90-30 PLC
Dwg 10 Boston Heights											
	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC						
	Hill 57 Booster Station MDS Repeater Radio	952TX/928RX MHz	Boston Heights MDS 9710b Radio	RS232	Boston Heights Versamax Micro PLC						
Dwg 11 Malmstrom AFB											
	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC						
	Hill 57 Booster Station MDS Repeater Radio	952TX/928RX MHz	Malmstrom AFB MDS 9710b Radio	RS232	Malmstrom AFB Versamax Micro PLC						
Dwg 12 Fire Station 1											
	Radio/PLC	Comm	Radio/PLC	Comm	Radio/PLC						
	Hill 57 Booster Station MDS Repeater Radio	952TX/928RX MHz	Fire Station 1 MDS 9710b Radio	RS232	Fire Station 1 Versamax Micro PLC						
8	90-30 PLCs										
4	Versamax Micro PLCs										
5	MDS 9710b radios										
7	MDS 9810b radios										
Note - Some equipment repeated on this and the Wired worksheets											

Overview




TITLE			
Water Treatment Plant Network Overview			
DESCRIPTION			
Graphical overview of Control/Business Network configuration			
DRAWN BY	REVISED	SCALE	PAGE
MIKE JENKINS	4/1/2010	1: 1	1 OF 12

Filter Bldg




TITLE			
Filter Building			
DESCRIPTION			
Network & Control System Detail			
DRAWN BY	REVISED	SCALE	PAGE
MIKE JENKINS	4/1/2010	1:1	2 OF 12

Pump Station




TITLE			
Pump Station Building			
DESCRIPTION			
Network & Control System Detail			
DRAWN BY	REVISED	SCALE	PAGE
MIKE JENKINS	4/1/2010	1: 1	3 OF 12

BW Clarifier




TITLE			
Backwash Clarifier Building			
DESCRIPTION			
Network & control system detail			
DRAWN BY	REVISED	SCALE	PAGE
MIKE JENKINS	4/1/2010	1: 1	4 OF 12

Head House



TITLE			
Head House			
DESCRIPTION			
Network & control system detail			
DRAWN BY	REVISED	SCALE	PAGE
MIKE JENKINS	4/1/2010	1:1	5 OF 12

Wireless SCADA




Notes

1. Modbus RTU communications speed is 9600 baud to all nodes
2. All remote nodes are configured as 'Slaves'
3. Double-click on RTU to go to details for remote site/ system.




TITLE			
Wireless SCADA			
DESCRIPTION			
Modbus Wireless Communications Overview			
DRAWN BY	REVISED	SCALE	PAGE
MIKE JENKINS	4/1/2010	1: 1	6 OF 12

Hill 57 Booster




TITLE			
Hill 57 Booster			
DESCRIPTION			
SCADA Communications Detail			
DRAWN BY	REVISED	SCALE	PAGE
MIKE JENKINS	4/1/2010	1:1	7 OF 12

Gore Hill Booster




TITLE			
Gore Hill Booster			
DESCRIPTION			
SCADA Communications Detail			
DRAWN BY	REVISED	SCALE	PAGE
MIKE JENKINS	4/1/2010	1: 1	8 OF 12

33rd St. Booster




TITLE			
33rd St. Booster			
DESCRIPTION			
SCADA Communications Detail			
DRAWN BY	REVISED	SCALE	PAGE
MIKE JENKINS	4/1/2010	1:1	9 OF 12

Boston Heights




TITLE			
Boston Heights			
DESCRIPTION			
SCADA Communications Detail			
DRAWN BY	REVISED	SCALE	PAGE
MIKE JENKINS	4/1/2010	1:1	10 OF 12

MAFB



TITLE			
MAFB			
DESCRIPTION			
SCADA Communications Detail			
DRAWN BY	REVISED	SCALE	PAGE
MIKE JENKINS	4/1/2010	1:1	11 OF 12

Fire Sta. 1



TITLE			
Fire Sta. 1			
DESCRIPTION			
SCADA Communications Detail			
DRAWN BY	REVISED	SCALE	PAGE
MIKE JENKINS	4/1/2010	1: 1	12 OF 12

Appendix E - Duties, Responsibilities and Limitations of Authority of the Special Inspections Representative

DUTIES, RESPONSIBILITIES AND
LIMITATIONS OF AUTHORITY OF THE
SPECIAL INSPECTIONS REPRESENTATIVE

1. Engineer will furnish a Special Inspections Representative and Special Inspectors. The Special Inspection Representative and Special Inspectors will observe the Contractor's work and perform the services listed in 01450 Structural Tests and Special Inspections. The Special Inspections Representative shall not have responsibility for the superintendence of construction site conditions, safety, safe practices or unsafe practices or conditions, operation, equipment, or personnel other than employees of the Engineer. This service will in no way relieve the Contractor of complete supervision and inspection of the work or the Contractor's obligation for complete compliance with the drawings and specifications. The Contractor shall have sole responsibility for safety and for maintaining safe practices and avoiding unsafe practices or conditions. Specific services performed by the Special Inspections Representative and Special Inspectors and durations of their services are as follows:

- | | |
|---------------------------------------|-----------|
| a. Special Inspections Representative | 24 Months |
| b. Concrete Inspector | 24 Months |
| c. Masonry Inspector | 24 Months |
| d. Geotechnical Inspector | 24 Months |

2. Site Observations and Liaison with Owner, Engineer, Authority Having Jurisdiction (AHJ), Inspection and Testing Agencies and Contractor(s)
 - a. Conduct onsite observations of the general progress of the testing and inspections to assist Engineer in determining if Structural Tests and Special Inspections are proceeding in accordance with the Special Inspections Program.
 - b. Serve as Engineer's liaison with the Authority Having Jurisdiction, and assist Engineer in providing thorough execution of the Special Inspections Program. Assemble and transmit interim inspection reports to the AHJ and Engineer in accordance with the schedule set forth in the Special Inspections Program.
 - c. Serving as Engineer's liaison with the Contractor when the testing and/or inspections activities must be coordinated with the Contractor's onsite operation.
 - d. Report to Engineer, giving opinions and suggestions based on the interim reporting received from the tests and inspections regarding defects or deficiencies in the

Contractor's work and relating to compliance with drawings, specifications, and design concepts.

- e. Advise Engineer, AHJ and the Contractor or its superintendent immediately of the presence of an unresolved deficiency in the work requiring resolution. Notify the Contractor of the need to correct the deficiency before proceeding with any activity that would encumber correcting the deficiency.
- f. Review the Contractors' construction sequence and coordinate the appropriate inspection and/or testing activities.
- g. Verify that the Contractor has contacted the Special Inspectors or Testing Agencies and advised them of Contractor's schedule. Assist in coordinating scheduling of inspections or tests to minimize impacts to the progress of the Work.
- h. Coordinate onsite structural testing services during construction. Copies of testing results will be forwarded to Special Inspectors for review and information.
- i. Observe the execution of the Special Inspections Program and review the resulting reports, commenting to Engineer, as appropriate.

3. Outside Liaison and Public Information Services

- a. Accompany visiting inspectors representing public or other agencies having jurisdiction over the project. Record the names of the inspectors, and the results of the inspections, and report to Engineer.

4. Meetings, Reports, and Document Review and Maintenance

- a. Attend the preconstruction conference, and assist Engineer in explaining administrative procedures of the Special Inspections Program that will be followed during construction.
- b. Attend monthly progress meetings, and other meetings with Owner, AHJ and the Contractor when necessary, to review and discuss progress of inspections and/or testing.
- c. Submit to Engineer, with a copy to AHJ, interim Special Inspections progress reports containing a summary of the Contractor's progress, general condition of the work, problems, and resolutions or proposed resolutions to problems.
- d. Notify Engineer regarding work which is reported to be defective, or which fails any required inspections, tests, or approvals; and advise Engineer of status of corrective action.
- e. Record date of receipt of inspection reports and test reports. Maintain records at the site for examination by Owner, AHJ, Inspectors, Contractor or Engineer.

- f. Maintain a marked set of drawings and specifications at the jobsite based on data provided by the Contractor and/or inspectors regarding noted deficiencies and the subsequent corrections to the Work. This information will be combined with information from the record documents maintained by the Contractor, and a master set of documents conforming to construction records will be produced.
5. Maintain the following documents at the jobsite.
 - a. Correspondence files.
 - b. Test Reports.
 - c. Manufacturer's Certificates of Compliance for items contained in the Statement of Special Inspections.
 - d. Reproductions of original construction contract documents.
 - e. Addenda.
 - f. Change orders.
 - g. Field orders.
 - h. Additional drawings issued subsequent to execution of the construction contract documents.
 - i. Inspection Reports.
 - j. Names, addresses, and telephone numbers of all Special Inspectors and Agencies conducting testing in accordance with the Special Inspections Program.
 6. Maintain a daily diary or log book of events at the jobsite. The diary or log book shall remain the property of Engineer. It will include the following information:
 - a. Days the Agencies or Inspectors worked on the jobsite.
 - b. Inspector and/or testing personnel on jobsite.
 - c. Testing or inspection equipment on the jobsite.
 - d. Weather conditions.
 - e. Observations pertaining to the progress of the inspections.

- f. Materials received on jobsite subject to 01450 Structural Tests and Special Inspections.

Appendix F - Duties, Responsibilities and Limitations of Authority of the Resident Project Representative

DUTIES, RESPONSIBILITIES AND
LIMITATIONS OF AUTHORITY OF THE
RESIDENT PROJECT REPRESENTATIVE

5. Engineer will furnish a Resident Project Representative. The Resident Project Representative will observe the Contractor's work and perform the services listed below. The Resident Project Representative shall not have responsibility for the superintendence of construction site conditions, safety, safe practices or unsafe practices or conditions, operation, equipment, or personnel other than employees of the Engineer. This service will in no way relieve the Contractor of complete supervision and inspection of the work or the Contractor's obligation for complete compliance with the drawings and specifications. The Contractor shall have sole responsibility for safety and for maintaining safe practices and avoiding unsafe practices or conditions. Specific services performed by the Resident Project Representative and assistants and durations of their services are as follows:
- a. Resident Project Representative 24 Months
6. Site Observations and Liaison with Owner and Contractor(s)
- a. Conduct onsite observations of the general progress of the work to assist Engineer in determining if the work is proceeding in accordance with the construction contract documents.
 - b. Serve as Engineer's liaison with the Contractor, working principally through the Contractor's superintendent, and assist Engineer in providing interpretation of the construction contract documents. Transmit Engineer's clarifications and interpretations of the construction contract documents to the Contractor.
 - c. Assist Engineer in serving as Owner's liaison with the Contractor when the Contractor's operations affect Owner's onsite operation.
 - d. As requested by Engineer, assist in obtaining from Owner additional details or information when required at the jobsite for proper execution of the work.
 - e. Report to Engineer, giving opinions and suggestions based on the Resident Project Representative's observations regarding defects or deficiencies in the Contractor's work and relating to compliance with drawings, specifications, and design concepts. These opinions and observations are exclusive of special inspections and structural observation to be conducted by others.
 - f. Advise Engineer and the Contractor or its superintendent immediately of the commencement of any work requiring a shop drawing or sample submission if the submission has not been accepted by Engineer.

- g. Monitor changes of apparent integrity of the site, such as differing subsurface and physical conditions, existing structures, and site-related utilities when such utilities are exposed.
- h. Observe pertinent site conditions when the Contractor maintains that differing subsurface and physical conditions have been encountered, and document actual site conditions. Review and analysis of the Contractor's claims for differing subsurface and physical conditions are supplemental services.
- i. Review the Contractors' construction sequence and traffic control plans for all construction work undertaken simultaneously.
- j. Verify that the Contractor has contacted utilities in the general construction area and advised them of Contractor's schedule. Assist in coordinating scheduling of utility activities to minimize conflicts with Owner's activities.
- k. Establish and furnish the Contractor with necessary baselines and control points that will be used as datum for the work. Actual construction staking will be done by the Contractor.
- l. Visually inspect materials, equipment, and supplies delivered to the worksite. Reject materials, equipment, and supplies that do not conform to the construction contract documents. These inspections are exclusive of special inspection activities performed by others.
- m. Coordinate onsite materials testing services during construction. Copies of testing results will be forwarded to Owner for review and information. Materials testing contained as part of special inspections are the responsibility of the approved agency conducting such work and reporting is made in accordance with the program for special inspections.
- n. Observe field tests of equipment, structures, and piping, and review the resulting reports, commenting to Engineer, as appropriate.

7. Outside Liaison and Public Information Services

- a. Accompany visiting inspectors representing public or other agencies having jurisdiction over the project. Record the names of the inspectors, and the results of the inspections, and report to Engineer.
- b. Provide personnel and facilities for dealing with telephoned or written complaints and other communications related to the construction of the project.
- c. Provide the necessary services in connection with public information and notification of individual property owners during construction.

8. Meetings, Reports, and Document Review and Maintenance

- a. Attend the preconstruction conference, and assist Engineer in explaining administrative procedures that will be followed during construction.
- b. Schedule and attend monthly progress meetings, and other meetings with Owner and the Contractor when necessary, to review and discuss construction procedures and progress scheduling, engineering management procedures, and other matters concerning the project.
- c. Submit to Engineer, with a copy to Owner, weekly construction progress reports containing a summary of the Contractor's progress, general condition of the work, problems, and resolutions or proposed resolutions to problems. Special inspections reports are submitted by others per schedule and procedures established in the program for special inspections.
- d. Review the progress schedule, schedule of shop drawings submissions, and schedule of values prepared by the Contractor, and consult with Engineer concerning their acceptability.
- e. Report to Engineer regarding work which is known to be defective, or which fails any required inspections, tests, or approvals, or has been damaged prior to final payment; and advise Engineer whether the work should be corrected or rejected, or should be uncovered for observation, or requires additional testing, inspection, or approval. The responsibilities of any special inspector or agent to report deficiencies in accordance with the program of special inspections is not to be amended or altered and may be the basis for the knowledge.
- f. Review applications for payment with the Contractor for compliance with the established procedure for their submission, and forward them with recommendations to Engineer, noting particularly their relation to the schedule of values, work completed, and materials and equipment delivered at the site, but not incorporated into the work.
- g. Record date of receipt of shop drawings and samples. Receive samples that are furnished at the site by the Contractor, and notify Engineer of their availability for examination.
- h. During the course of the work, verify that specified certificates, operation and maintenance manuals, and other data required to be assembled and furnished by the Contractor are applicable to the items actually installed; and deliver this material to Engineer for his review and forwarding to Owner prior to final acceptance of the work. This is exclusive of any verifications contained as part of the program of special inspections.
- i. Maintain a marked set of drawings and specifications at the jobsite based on data provided by the Contractor. This information will be combined with information from

the record documents maintained by the Contractor, and a master set of documents conforming to construction records will be produced.

- j. Review certificates of inspections, tests, and related approvals submitted by the Contractor as required by laws, rules, regulations, ordinances, codes, orders, or the Contract Documents (but only to verify that their content complies with the requirements of, and the results certified indicate compliance with, the construction contract documents). This service is limited to a review of items submitted by the Contractor and does not extend to a determination of whether the Contractor has complied with all legal requirements. This is exclusive of items contained in the program of special inspections reviewed or verified by others.

5. Maintain the following documents at the jobsite.

- k. Correspondence files.

- l. Reports of jobsite conferences, meetings, and discussions among the Engineer, Owner, and Contractor.

- m. Submittals of shop drawings and samples.

- n. Reproductions of original construction contract documents.

- o. Addenda.

- p. Change orders.

- q. Field orders.

- r. Additional drawings issued subsequent to execution of the construction contract documents.

- s. Progress reports.

- t. Names, addresses, and telephone numbers of all contractors, subcontractors, and major suppliers of materials and equipment.

6. Maintain a daily diary or log book of events at the jobsite. The diary or log book shall remain the property of Engineer. It will include the following information:

- g. Days the Contractor worked on the jobsite.

- h. Contractor and subcontractor personnel on jobsite.

- i. Construction equipment on the jobsite.

- j. Observed delays and causes.
- k. Weather conditions.
- l. Data relative to claims for extras or deductions.
- m. Daily activities.
- n. Observations pertaining to the progress of the work.
- o. Materials received on jobsite.


7. Assistance in Certification of Substantial Completion

- a. Before Engineer issues a Certificate of Substantial Completion, submit to the Contractor a list of items observed to require completion or correction.
- b. Assist Engineer in conducting final inspection in the company of Owner and the Contractor, and prepare a final list of items to be completed or corrected.
- c. Verify that all items on the final list have been completed or corrected, and make recommendations to Engineer concerning acceptance.

Great Falls Montana WTP Facility Upgrade Project - Phase 1

Schedule v4 - Based on Revised BIM Workflow Model

Detailed Design and Bidding Phases



Great Falls Montana WTP Facility Upgrade Project - Phase 1

Schedule v4 - Based on Revised BIM Workflow Model


Detailed Design and Bidding Phases

ID	Task Name	Start	Finish	2015												2016								
				3rd Quarter			4th Quarter			1st Quarter			2nd Quarter			3rd Quarter			4th Quarter			1st Quarter		
				Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar
111	Preliminary Geotechnical Information	Wed 11/5/14	Tue 12/2/14						12/2															
112	Chemical Feed Schematics	Wed 11/5/14	Tue 11/18/14						11/18															
113	Chemical Feed Criteria Tables	Wed 11/5/14	Mon 11/10/14						11/10															
114	Equipment Tagging Standards	Wed 11/5/14	Tue 11/18/14						11/18															
115	Discipline Design Guidelines and Criteria	Wed 11/5/14	Tue 12/2/14						12/2															
116	Designer Response to City Review Comments on Draft Phase 1 Drawings for Task 282C	Wed 11/5/14	Tue 12/9/14						12/9															
117	Consolidated Basis of Design Memo	Wed 12/3/14	Thu 1/22/15																					
118	Prepare Draft	Wed 12/3/14	Fri 12/12/14						12/12															
119	Holiday Allowance	Mon 12/15/14	Fri 12/26/14																					
120	Internal QA/QC & Revisions	Mon 12/29/14	Fri 1/2/15						1/2															
121	City Review	Mon 1/5/15	Fri 1/9/15																					
122	City Review Comments on 30% Detailed Design Package	Fri 1/9/15	Fri 1/9/15																					
123	Review Meeting to discuss City review comments	Thu 1/15/15	Thu 1/15/15																					
124	Final Basis of Design Memo	Fri 1/16/15	Thu 1/22/15																					
125	320 - 30% Detailed Design	Fri 1/16/15	Tue 3/17/15																					
126	Front End Contract Documents	Fri 1/16/15	Wed 2/4/15																					
127	Civil/Site Drawings	Fri 1/16/15	Thu 1/22/15																					
128	Geotechnical Report	Fri 1/16/15	Thu 2/5/15																					
129	Draft Report	Fri 1/16/15	Thu 1/22/15																					
130	City Review	Fri 1/23/15	Thu 1/29/15																					
131	Final Report	Fri 1/30/15	Thu 2/5/15																					
132	Final Hydraulic Profile	Fri 1/16/15	Tue 1/27/15																					
133	Process Equipment Specifications	Fri 1/16/15	Thu 2/5/15																					
134	Architectural CAD Plans for Buildings	Fri 1/16/15	Thu 1/22/15																					
135	Architectural Elevations	Fri 1/23/15	Tue 1/27/15																					
136	Prelim Structural Design	Fri 1/23/15	Thu 2/5/15																					
137	Column Row Locations & Floor Elevations	Fri 1/23/15	Wed 1/28/15																					
138	Code Classification Table	Fri 1/16/15	Thu 1/22/15																					
139	Locate HVAC & Plumbing Equipment	Fri 1/23/15	Thu 1/29/15																					
140	Locate Electrical & I&C Equipment	Fri 1/23/15	Thu 1/29/15																					
141	Updated Power Distribution Diagram	Fri 1/16/15	Wed 1/21/15																					
142	Update Control System Block Diagram	Fri 1/16/15	Wed 1/21/15																					
143	Updated P&IDS and Control Descriptions	Fri 1/16/15	Thu 1/29/15																					
144	I&C I/O Lists & Device Schedules	Fri 1/16/15	Thu 1/22/15																					
145	Updated Construction Cost Estimate	Fri 2/6/15	Mon 2/16/15																					
146	Compile 30% Design Package	Tue 2/10/15	Wed 2/18/15																					
147	Internal QA/QC Review and Package Revision	Thu 2/19/15	Wed 2/25/15																					
148	Designer response to City Review Comments on 15% Design Package	Fri 1/16/15	Thu 2/19/15																					
149	City Review of 30% Design Package	Thu 2/26/15	Wed 3/11/15																					
150	City Review Comments on 30% Design Package	Wed 3/11/15	Wed 3/11/15																					
151	Review Meeting to discuss City review comments	Tue 3/17/15	Tue 3/17/15																					
152	330 - 60% Detailed Design	Wed 3/18/15	Fri 6/26/15																					
153	Updated Civil/Site Drawings & Details	Wed 3/18/15	Tue 3/31/15																					
154	Yard Piping & Underground Utility Drawings	Wed 3/18/15	Wed 3/25/15																					
155	Equipment & Piping Floor Plans	Wed 3/18/15	Tue 3/24/15																					

City of Great Falls
WTP Facility Upgrade Project
Level of Effort and Fee Estimate Summary

	HOURS						LABOR COST						TOTAL EXPENSE S	TOTAL COST
	B&V	TD&H	LPW	IAC	Bill Knoll	TOTAL	B&V	TD&H	LPW	IAC	Bill Knoll	TOTAL		
DETAILED DESIGN AND BIDDING PHASE	10,458	5,312	2,061	1,013	398	19,282	\$1,566,862	\$517,942	\$165,752	\$131,625	\$41,790	\$2,423,971	\$310,696	\$2,734,667
110A - AMEND PROJECT WORKPLAN	68	26	8	0	0	102	\$10,024	\$3,056	\$912	\$0	\$0	\$13,992	\$706	\$14,698
190D - CONT'D PROJECT MANAGEMENT & CONTROLS	836	267	57	0	0	1,160	\$132,040	\$30,894	\$6,498	\$0	\$0	\$169,432	\$4,480	\$173,912
PLC MIGRATION PLAN	222	0	0	589	0	811	\$37,984	\$0	\$0	\$73,625	\$0	\$111,609	\$6,233	\$117,842
289A - OWNER COMMISSION PRESENTATIONS	24	32	16	0	0	72	\$4,656	\$3,588	\$1,616	\$0	\$0	\$9,860	\$4,266	\$14,126
290A - CONT'D DETERMINE LOCATION OF UTILITIES	16	86	0	0	0	102	\$2,728	\$7,316	\$0	\$0	\$0	\$10,044	\$1,156	\$11,200
294B - CONT'D COORD. WITH NW ENERGY	700	8	0	0	0	708	\$104,400	\$936	\$0	\$0	\$0	\$105,336	\$14,124	\$119,460
295 - REVIEW OF DESIGN DELIVERABLES BY IAC	64	0	0	158	0	222	\$9,524	\$0	\$0	\$19,750	\$0	\$29,274	\$766	\$30,040
301 - CONDUCT HAZARD MTLs ASSESSMENT	8	156	0	0	0	164	\$1,552	\$16,104	\$0	\$0	\$0	\$17,656	\$2,292	\$19,948
302A - CONT'D PERMIT. ASST. WITH MDEQ	420	48	0	0	0	468	\$69,800	\$4,944	\$0	\$0	\$0	\$74,744	\$4,504	\$79,248
303 - ON-CALL SURVEYING	0	88	0	0	0	88	\$0	\$7,496	\$0	\$0	\$0	\$7,496	\$2,014	\$9,510
304 - PREPARE CONTRACTOR INFO FOR IAC	136	0	0	250	0	386	\$20,500	\$0	\$0	\$31,250	\$0	\$51,750	\$1,558	\$53,308
306 - PREPARE CONTRACTOR INFO FOR WEDECO	220	0	0	0	0	220	\$35,200	\$0	\$0	\$0	\$0	\$35,200	\$57,660	\$92,860
308 - TESTING OF ELECTRICAL GROUNDING	26	0	0	0	0	26	\$4,292	\$0	\$0	\$0	\$0	\$4,292	\$4,278	\$8,570
310 - 15% DETAILED DESIGN	683	735	193	16	20	1,647	\$101,334	\$71,150	\$17,449	\$2,000	\$2,100	\$194,033	\$40,691	\$234,724
320 - 30% DETAILED DESIGN	1,207	1,218	262	0	82	2,769	\$178,724	\$115,447	\$20,710	\$0	\$8,610	\$323,491	\$24,207	\$347,698
330 - 60% DETAILED DESIGN	1,947	1,021	590	0	136	3,694	\$288,500	\$101,039	\$45,310	\$0	\$14,280	\$449,129	\$31,282	\$480,411
340 - 90% DESIGN PACKAGE	1,887	705	586	0	0	3,178	\$276,974	\$68,044	\$45,062	\$0	\$0	\$390,080	\$18,334	\$408,414
345 - 90% QA/QC REVIEW & PERMIT. AGENCY REVIEW	360	453	89	0	160	1,062	\$53,924	\$42,500	\$7,101	\$0	\$16,800	\$120,325	\$9,386	\$129,711
350 - 100% DESIGN PACKAGE	814	190	58	0	0	1,062	\$118,348	\$17,022	\$5,052	\$0	\$0	\$140,422	\$5,386	\$145,808
360 - BIDDING ASSISTANCE AND CONTRACTING	280	43	42	0	0	365	\$34,848	\$5,010	\$4,242	\$0	\$0	\$44,100	\$4,445	\$48,545
361 - CONTINGENCY FOR DETAILED DESIGN	540	236	160	0	0	976	\$81,510	\$23,396	\$11,800	\$5,000	\$0	\$121,706	\$72,928	\$194,634
CONSTRUCTION AND COMMISSIONING PHASE	5,512	13,768	923	0	0	20,203	\$862,690	\$1,293,202	\$79,470	\$0	\$0	\$2,235,362	\$274,109	\$2,509,471
190E - CONT'D PROJECT MANAGEMENT & CONTROLS	1,618	403	163	0	0	2,184	\$249,738	\$47,647	\$14,100	\$0	\$0	\$311,485	\$26,552	\$338,037
410 - CONSTRUCTION ADMINISTRATION SERVICES	2,416	3,665	336	0	0	6,417	\$366,994	\$362,381	\$30,114	\$0	\$0	\$759,489	\$60,051	\$819,540
420 - FIELD SUPPORT SERVICES	62	1,431	210	0	0	1,703	\$10,506	\$167,489	\$19,026	\$0	\$0	\$197,021	\$56,109	\$253,130
425 - STRUCTURAL TESTS & SPECIAL INSPECTIONS	0	2,480	14	0	0	2,494	\$0	\$214,550	\$1,430	\$0	\$0	\$215,980	\$32,982	\$248,962
430 - ONSITE RESIDENT PROJECT REPRESENTATIVE	0	5,000	0	0	0	5,000	\$0	\$420,000	\$0	\$0	\$0	\$420,000	\$23,000	\$443,000
440 - O&M MANUALS	612	0	0	0	0	612	\$102,668	\$0	\$0	\$0	\$0	\$102,668	\$9,036	\$111,704
450 - STARTUP ASSIST., TRAINING & POST CONSTRUCTION	368	209	0	0	0	577	\$63,676	\$21,795	\$0	\$0	\$0	\$85,471	\$12,731	\$98,202
451 - CONTINGENCY FOR CONSTRUCTION	436	580	200	0	0	1,216	\$69,108	\$59,340	\$14,800	\$0	\$0	\$143,248	\$53,648	\$196,896
TOTAL	15,970	19,080	2,984	1,013	398	39,485	\$2,429,552	\$1,811,144	\$245,222	\$131,625	\$41,790	\$4,659,333	\$584,805	\$5,244,138

J:\2012\12-164 GTF WTP Upgrades\CADD\CIVIL\TASK 282C - Amend Project Implementation\12-164-282C-BM.dwg, 9/16/2014 10:00:09 AM, mwc




FUTURE PH.	BASE BID	EXISTING	DESCRIPTION
[Symbol]	[Symbol]	[Symbol]	ASPHALT PAVEMENT
[Symbol]	[Symbol]	[Symbol]	BOLLARDS
[Symbol]	[Symbol]	[Symbol]	BUILDING
[Symbol]	[Symbol]	[Symbol]	BUSH OR SHRUB
[Symbol]	[Symbol]	[Symbol]	CONCRETE
[Symbol]	[Symbol]	[Symbol]	CONTROL POINT
[Symbol]	[Symbol]	[Symbol]	CURB BOX
[Symbol]	[Symbol]	[Symbol]	CURB & GUTTER
[Symbol]	[Symbol]	[Symbol]	EDGE OF ASPHALT
[Symbol]	[Symbol]	[Symbol]	EDGE OF GRAVEL
[Symbol]	[Symbol]	[Symbol]	ELECTRICAL BOX

FUTURE PH.	BASE BID	EXISTING	DESCRIPTION
[Symbol]	[Symbol]	[Symbol]	FENCE - CHAIN LINK
[Symbol]	[Symbol]	[Symbol]	FIRE HYDRANT
[Symbol]	[Symbol]	[Symbol]	GAS
[Symbol]	[Symbol]	[Symbol]	GAS METER
[Symbol]	[Symbol]	[Symbol]	GATE
[Symbol]	[Symbol]	[Symbol]	GRAVEL SURFACING
[Symbol]	[Symbol]	[Symbol]	RAILROAD
[Symbol]	[Symbol]	[Symbol]	GUY WIRE
[Symbol]	[Symbol]	[Symbol]	HEDGE
[Symbol]	[Symbol]	[Symbol]	INLET
[Symbol]	[Symbol]	[Symbol]	IRRIGATION VALVE

FUTURE PH.	BASE BID	EXISTING	DESCRIPTION
[Symbol]	[Symbol]	[Symbol]	IRRIGATION LINE
[Symbol]	[Symbol]	[Symbol]	LIGHT POLE
[Symbol]	[Symbol]	[Symbol]	MANHOLE
[Symbol]	[Symbol]	[Symbol]	OVERHEAD ELECTRIC
[Symbol]	[Symbol]	[Symbol]	PARKING BLOCKS
[Symbol]	[Symbol]	[Symbol]	POWER POLE
[Symbol]	[Symbol]	[Symbol]	RAILROAD
[Symbol]	[Symbol]	[Symbol]	RETAINING WALL
[Symbol]	[Symbol]	[Symbol]	SANITARY SEWER
[Symbol]	[Symbol]	[Symbol]	SPRINKLER

FUTURE PH.	BASE BID	EXISTING	DESCRIPTION
[Symbol]	[Symbol]	[Symbol]	STORM DRAIN
[Symbol]	[Symbol]	[Symbol]	TELEPHONE RISER
[Symbol]	[Symbol]	[Symbol]	TRAFFIC SIGN
[Symbol]	[Symbol]	[Symbol]	TREE - CONIFEROUS
[Symbol]	[Symbol]	[Symbol]	TREE - DECIDUOUS
[Symbol]	[Symbol]	[Symbol]	UNDERGROUND ELECTRIC
[Symbol]	[Symbol]	[Symbol]	UNDERGROUND TELEPHONE
[Symbol]	[Symbol]	[Symbol]	VALVE
[Symbol]	[Symbol]	[Symbol]	WATERLINE
[Symbol]	[Symbol]	[Symbol]	FLOOD PLAIN



PIPING ABBREVIATIONS

LSD	LOW SERVICE DISCHARGE
RW	RAW WATER
FE	FILTER EFFLUENT
FW	FINISHED WATER
BWS	BACKWASH SUPPLY
D	DRAIN
OF	OVERFLOW
SE	SECONDARY EFFLUENT

LEGEND

DESIGNED: DDN	NO. BY CK APP
DETAILED: MWC	DATE
CHECKED:	REVISIONS AND RECORD OF ISSUE
APPROVED:	DATE
DATE: 08.1.14	NO. BY CK APP
0 1/2 1	NO. BY CK APP
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE	NO. BY CK APP
PROJECT NO. O.F. 1519.0	NO. BY CK APP
TDM #12-164	NO. BY CK APP
SD-1	NO. BY CK APP


BLACK & VEATCH
Building a world of difference

TD&H
Engineering & Construction


CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1
PRELIMINARY SITE PLAN
WEST AREA - BASE BID

L'Heureux Page Werner
Engineering & Construction

J:\2012\12-164 GTF WTP Upgrades\CADD\CIVIL\TASK 282C - Amend Project Implementation\12-164-282C-BM.dwg, 9/16/2014 10:00:11 AM, mwc



NOTE: CLOUDED FEATURES ON THIS SHEET ARE ALTERNATE BID ITEM NO. 1.



PIPING ABBREVIATIONS

LSD	LOW SERVICE DISCHARGE
RW	RAW WATER
FE	FILTER EFFLUENT
FW	FINISHED WATER
BWS	BACKWASH SUPPLY
D	DRAIN
OF	OVERFLOW
SE	SECONDARY EFFLUENT

LEGEND

BID ALTER.	FUTURE PH.	BASE BID	EXISTING	DESCRIPTION	BID ALTER.	FUTURE PH.	BASE BID	EXISTING	DESCRIPTION	BID ALTER.	FUTURE PH.	BASE BID	EXISTING	DESCRIPTION	BID ALTER.	FUTURE PH.	BASE BID	EXISTING	DESCRIPTION
[Symbol]	[Symbol]	[Symbol]	[Symbol]	ASPHALT PAVEMENT	[Symbol]	[Symbol]	[Symbol]	[Symbol]	FENCE - CHAIN LINK	[Symbol]	[Symbol]	[Symbol]	[Symbol]	IRRIGATION LINE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	STORM DRAIN
[Symbol]	[Symbol]	[Symbol]	[Symbol]	BOLLARDS	[Symbol]	[Symbol]	[Symbol]	[Symbol]	FIRE HYDRANT	[Symbol]	[Symbol]	[Symbol]	[Symbol]	LIGHT POLE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	TELEPHONE RISER
[Symbol]	[Symbol]	[Symbol]	[Symbol]	BUILDING	[Symbol]	[Symbol]	[Symbol]	[Symbol]	GAS	[Symbol]	[Symbol]	[Symbol]	[Symbol]	MANHOLE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	TRAFFIC SIGN
[Symbol]	[Symbol]	[Symbol]	[Symbol]	BUSH OR SHRUB	[Symbol]	[Symbol]	[Symbol]	[Symbol]	GAS METER	[Symbol]	[Symbol]	[Symbol]	[Symbol]	OVERHEAD ELECTRIC	[Symbol]	[Symbol]	[Symbol]	[Symbol]	TREE - CONIFEROUS
[Symbol]	[Symbol]	[Symbol]	[Symbol]	CONCRETE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	GATE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	PAINT STRIPE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	TREE - DECIDUOUS
[Symbol]	[Symbol]	[Symbol]	[Symbol]	CONTROL POINT	[Symbol]	[Symbol]	[Symbol]	[Symbol]	GRAVEL SURFACING	[Symbol]	[Symbol]	[Symbol]	[Symbol]	PARKING BLOCKS	[Symbol]	[Symbol]	[Symbol]	[Symbol]	UNDERGROUND ELECTRIC
[Symbol]	[Symbol]	[Symbol]	[Symbol]	CURB BOX	[Symbol]	[Symbol]	[Symbol]	[Symbol]	GUARD RAIL	[Symbol]	[Symbol]	[Symbol]	[Symbol]	POWER POLE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	UNDERGROUND TELEPHONE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	CURB & GUTTER	[Symbol]	[Symbol]	[Symbol]	[Symbol]	GUY WIRE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	RAILROAD	[Symbol]	[Symbol]	[Symbol]	[Symbol]	VALVE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	EDGE OF ASPHALT	[Symbol]	[Symbol]	[Symbol]	[Symbol]	HEDGE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	RETAINING WALL	[Symbol]	[Symbol]	[Symbol]	[Symbol]	WATERLINE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	EDGE OF GRAVEL	[Symbol]	[Symbol]	[Symbol]	[Symbol]	INLET	[Symbol]	[Symbol]	[Symbol]	[Symbol]	SANITARY SEWER	[Symbol]	[Symbol]	[Symbol]	[Symbol]	FLOOD PLAIN
[Symbol]	[Symbol]	[Symbol]	[Symbol]	ELECTRICAL BOX	[Symbol]	[Symbol]	[Symbol]	[Symbol]	IRRIGATION VALVE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	SPRINKLER	[Symbol]	[Symbol]	[Symbol]	[Symbol]	[Symbol]

DESIGNED: DDM	REVISIONS AND RECORD OF ISSUE	NO.	BY	CHK	APP
DATE: 08.1.14	DATE				
DETAILS: MWC	SAVED:				
CHECKED:	PLOTTED:				
APPROVED:	USER:				
DATE: 08.1.14	REF1:				
	REF2:				
	REF3:				
	REF4:				
	DWG. VER.:				

BLACK & VEATCH
Building a world of difference


L'Heureux Page Werner

TD&H
Engineering & Construction

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1
PRELIMINARY SITE PLAN
WEST AREA - BASE BID + BID ALTERNATES

SD-1A

J:\2012\12-164 GTF WTP Upgrades\CADD\CIVIL\TASK 282C - Amend Project Implementation\12-164-282C-BM.dwg, 9/16/2014 10:00:13 AM, mwc




BID ALTER.	FUTURE PH.	BASE BID	EXISTING	DESCRIPTION
[Symbol]	[Symbol]	[Symbol]	[Symbol]	ASPHALT PAVEMENT
[Symbol]	[Symbol]	[Symbol]	[Symbol]	BOLLARDS
[Symbol]	[Symbol]	[Symbol]	[Symbol]	BUILDING
[Symbol]	[Symbol]	[Symbol]	[Symbol]	BUSH OR SHRUB
[Symbol]	[Symbol]	[Symbol]	[Symbol]	CONCRETE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	CONTROL POINT
[Symbol]	[Symbol]	[Symbol]	[Symbol]	CURB BOX
[Symbol]	[Symbol]	[Symbol]	[Symbol]	CURB & GUTTER
[Symbol]	[Symbol]	[Symbol]	[Symbol]	EDGE OF ASPHALT
[Symbol]	[Symbol]	[Symbol]	[Symbol]	EDGE OF GRAVEL
[Symbol]	[Symbol]	[Symbol]	[Symbol]	ELECTRICAL BOX

BID ALTER.	FUTURE PH.	BASE BID	EXISTING	DESCRIPTION
[Symbol]	[Symbol]	[Symbol]	[Symbol]	FENCE - CHAIN LINK
[Symbol]	[Symbol]	[Symbol]	[Symbol]	FIRE HYDRANT
[Symbol]	[Symbol]	[Symbol]	[Symbol]	GAS
[Symbol]	[Symbol]	[Symbol]	[Symbol]	GAS METER
[Symbol]	[Symbol]	[Symbol]	[Symbol]	GATE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	GRAVEL SURFACING
[Symbol]	[Symbol]	[Symbol]	[Symbol]	GUARD RAIL
[Symbol]	[Symbol]	[Symbol]	[Symbol]	GUY WIRE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	HEDGE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	INLET
[Symbol]	[Symbol]	[Symbol]	[Symbol]	IRRIGATION VALVE

BID ALTER.	FUTURE PH.	BASE BID	EXISTING	DESCRIPTION
[Symbol]	[Symbol]	[Symbol]	[Symbol]	IRRIGATION LINE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	LIGHT POLE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	MANHOLE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	OVERHEAD ELECTRIC
[Symbol]	[Symbol]	[Symbol]	[Symbol]	PAINT STRIPE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	PARKING BLOCKS
[Symbol]	[Symbol]	[Symbol]	[Symbol]	POWER POLE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	RAILROAD
[Symbol]	[Symbol]	[Symbol]	[Symbol]	RETAINING WALL
[Symbol]	[Symbol]	[Symbol]	[Symbol]	SANITARY SEWER
[Symbol]	[Symbol]	[Symbol]	[Symbol]	SPRINKLER

BID ALTER.	FUTURE PH.	BASE BID	EXISTING	DESCRIPTION
[Symbol]	[Symbol]	[Symbol]	[Symbol]	STORM DRAIN
[Symbol]	[Symbol]	[Symbol]	[Symbol]	TELEPHONE RISER
[Symbol]	[Symbol]	[Symbol]	[Symbol]	TRAFFIC SIGN
[Symbol]	[Symbol]	[Symbol]	[Symbol]	TREE - CONIFEROUS
[Symbol]	[Symbol]	[Symbol]	[Symbol]	TREE - DECIDUOUS
[Symbol]	[Symbol]	[Symbol]	[Symbol]	UNDERGROUND ELECTRIC
[Symbol]	[Symbol]	[Symbol]	[Symbol]	UNDERGROUND TELEPHONE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	VALVE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	WATERLINE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	FLOOD PLAIN




PIPING ABBREVIATIONS

LSD	LOW SERVICE DISCHARGE
RW	RAW WATER
FE	FILTER EFFLUENT
FW	FINISHED WATER
BWS	BACKWASH SUPPLY
D	DRAIN
OF	OVERFLOW
SE	SECONDARY EFFLUENT


LEGEND

NO.	BY	CHK	APP	REVISIONS AND RECORD OF ISSUE			
DATE	SAVED:	PLOTTED:	USER:	DATE			
				XREF1:			
				XREF2:			
				XREF3:			
				XREF4:			
				DWG. VER.:			
CITY OF GREAT FALLS, MONTANA WATER TREATMENT PLANT FACILITY UPGRADES - PHASE 1 PRELIMINARY SITE PLAN CENTRAL AREA - BASE BID + BID ALTERNATES							
DESIGNED: DDM DETAILED: MWC CHECKED: APPROVED: DATE: 08.1.14							
<p>IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE</p>							
PROJECT NO. O.F. 1519.0 T&H #12-164							
SD-2							

J:\2012\12-164 GTF WTP Upgrades\CADD\CIVIL\TASK 282C - Amend Project Implementation\12-164-282C-BM.dwg, 9/16/2014 10:00:15 AM, mwc



NOTE: CLOUDED FEATURES ON THIS SHEET ARE ALTERNATE BID ITEM NO. 2.




PIPING ABBREVIATIONS

LSD	LOW SERVICE DISCHARGE
RW	RAW WATER
FE	FILTER EFFLUENT
FW	FINISHED WATER
BWS	BACKWASH SUPPLY
D	DRAIN
OF	OVERFLOW
SE	SECONDARY EFFLUENT


LEGEND

BID ALTER.	FUTURE PH.	BASE BID	EXISTING	DESCRIPTION	BID ALTER.	FUTURE PH.	BASE BID	EXISTING	DESCRIPTION	BID ALTER.	FUTURE PH.	BASE BID	EXISTING	DESCRIPTION	BID ALTER.	FUTURE PH.	BASE BID	EXISTING	DESCRIPTION
[Symbol]	[Symbol]	[Symbol]	[Symbol]	ASPHALT PAVEMENT	[Symbol]	[Symbol]	[Symbol]	[Symbol]	FENCE - CHAIN LINK	[Symbol]	[Symbol]	[Symbol]	[Symbol]	IRRIGATION LINE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	STORM DRAIN
[Symbol]	[Symbol]	[Symbol]	[Symbol]	BOLLARDS	[Symbol]	[Symbol]	[Symbol]	[Symbol]	FIRE HYDRANT	[Symbol]	[Symbol]	[Symbol]	[Symbol]	LIGHT POLE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	TELEPHONE RISER
[Symbol]	[Symbol]	[Symbol]	[Symbol]	BUILDING	[Symbol]	[Symbol]	[Symbol]	[Symbol]	GAS	[Symbol]	[Symbol]	[Symbol]	[Symbol]	MANHOLE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	TRAFFIC SIGN
[Symbol]	[Symbol]	[Symbol]	[Symbol]	BUSH OR SHRUB	[Symbol]	[Symbol]	[Symbol]	[Symbol]	GAS METER	[Symbol]	[Symbol]	[Symbol]	[Symbol]	OVERHEAD ELECTRIC	[Symbol]	[Symbol]	[Symbol]	[Symbol]	TREE - CONIFEROUS
[Symbol]	[Symbol]	[Symbol]	[Symbol]	CONCRETE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	GATE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	PAINT STRIPE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	TREE - DECIDUOUS
[Symbol]	[Symbol]	[Symbol]	[Symbol]	CONTROL POINT	[Symbol]	[Symbol]	[Symbol]	[Symbol]	GRAVEL SURFACING	[Symbol]	[Symbol]	[Symbol]	[Symbol]	PARKING BLOCKS	[Symbol]	[Symbol]	[Symbol]	[Symbol]	UNDERGROUND ELECTRIC
[Symbol]	[Symbol]	[Symbol]	[Symbol]	CURB BOX	[Symbol]	[Symbol]	[Symbol]	[Symbol]	GUARD RAIL	[Symbol]	[Symbol]	[Symbol]	[Symbol]	POWER POLE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	UNDERGROUND TELEPHONE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	CURB & GUTTER	[Symbol]	[Symbol]	[Symbol]	[Symbol]	GUY WIRE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	RAILROAD	[Symbol]	[Symbol]	[Symbol]	[Symbol]	VALVE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	EDGE OF ASPHALT	[Symbol]	[Symbol]	[Symbol]	[Symbol]	HEDGE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	RETAINING WALL	[Symbol]	[Symbol]	[Symbol]	[Symbol]	WATERLINE
[Symbol]	[Symbol]	[Symbol]	[Symbol]	EDGE OF GRAVEL	[Symbol]	[Symbol]	[Symbol]	[Symbol]	INLET	[Symbol]	[Symbol]	[Symbol]	[Symbol]	SANITARY SEWER	[Symbol]	[Symbol]	[Symbol]	[Symbol]	FLOOD PLAIN
[Symbol]	[Symbol]	[Symbol]	[Symbol]	ELECTRICAL BOX	[Symbol]	[Symbol]	[Symbol]	[Symbol]	IRRIGATION VALVE	[Symbol]	[Symbol]	[Symbol]	[Symbol]	SPRINKLER	[Symbol]	[Symbol]	[Symbol]	[Symbol]	[Symbol]

NO.	BY	CHK	APP	REVISIONS AND RECORD OF ISSUE			
DATE	SAVED:	PLOTTED:	USER:	DATE	SAVED:	PLOTTED:	USER:
CITY OF GREAT FALLS, MONTANA WATER TREATMENT PLANT FACILITY UPGRADES - PHASE 1 PRELIMINARY SITE PLAN EAST AREA - BASE BID + BID ALTERNATES							
DESIGNED: DDM DETAILED: MWC CHECKED: APPROVED: DATE: 08.1.14							
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE							
PROJECT NO. O.F. 1519.0 TDR #12-164							
SD-3							



1 LONGITUDINAL BUILDING SECTION
1/8" = 1'-0"



2 TRANSVERSE BUILDING SECTION
1/8" = 1'-0"

NO.	BY	CHK	APP

DATE	REVISIONS AND RECORD OF ISSUE

SAVED:	PLOTTED:	USER:	DWG. VER:

BLACK & VEATCH
B


L'Heureux Page Werner
LPW

TD&H
Engineering Consultants
Thomas, Dorn & Herbstein, Inc.

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1


CHEMICAL FEED AND UV DISINFECTION BUILDING
BUILDING SECTIONS

DESIGNED: _____
 DETAILED: _____
 CHECKED: _____
 APPROVED: _____
 DATE: _____




PROJECT NO.
O.F. 1519.0
LPW #12-039


AC-2



1 NORTH ELEVATION
1/8" = 1'-0"




2 EAST ELEVATION
1/8" = 1'-0"



3 SOUTH ELEVATION
1/8" = 1'-0"

EXTERIOR FINISH SCHEDULE		
Mark	Description	Comments
1	METAL SIDING	
2	BRICK	
D		




4 WEST ELEVATION
1/8" = 1'-0"


DATE	REVISED AND RECORD OF ISSUE	NO.	BY	APP.

SAVED: XREF1:
PLOTTED: XREF2:
USER: XREF3:
LWE: VER: XREF4:

BLACK & VEATCH




L'Heureux Page Werner




CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1

CHEMICAL FEED AND UV DISINFECTION BUILDING
EXTERIOR ELEVATIONS

DESIGNED:
DETAILED:
CHECKED:
APPROVED:
DATE:



PROJECT NO.
O.F. 1519.0
LPW #12-039



1 ELECTRICAL ROOM BASEMENT LEVEL
 1/8" = 1'-0"



DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	APP.

BLACK & VEATCH


TD&H
 Thomas, Dean & Hordley, Inc.
 Engineering Consultants

L'Heureux Page Werner

CITY OF GREAT FALLS, MONTANA
 WATER TREATMENT PLANT
 FACILITY UPGRADES - PHASE 1

ELECTRICAL ROOM ADDITION
 BASEMENT LEVEL FLOOR PLAN

DESIGNED:
DETAILED:
CHECKED:
APPROVED:
DATE:
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE
PROJECT NO. O.F. 1519.0 LPW #12-039
AP-1



1 ELECTRICAL ROOM MAIN LEVEL
1/8" = 1'-0"



NO.	BY	CHK	APP

BLACK & VEATCH


L'Heureux Page Werner

TD&H
 Thomas, Dean & Hopkins, Inc.
 Engineering Consultants


CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1
ELECTRICAL ROOM ADDITION
 MAIN LEVEL FLOOR PLAN

DESIGNED:
DETAILED:
CHECKED:
APPROVED:
DATE:
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE
PROJECT NO.
O.F. 1519.0
LPW #12-039
AP-2

D7075



1 ELECTRICAL ROOM MAIN LEVEL - WITH ALTERNATE BID ITEMS
 1/8" = 1'-0"



NO.	BY	CHK	APP

BLACK & VEATCH

L'Heureux Page Werner


TD&H
 Thomas, Dean & Hordtke, Inc.
 Engineering Consultants

CITY OF GREAT FALLS, MONTANA
 WATER TREATMENT PLANT
 FACILITY UPGRADES - PHASE 1


ELECTRICAL ROOM ADDITION
 MAIN LEVEL FLOOR PLAN - BASE BID + BID ALTERNATES

DESIGNED:
DETAILED:
CHECKED:
APPROVED:
DATE:
0 1/2 1
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE
PROJECT NO. O.F. 1519.0
LPW #12-039
AP-2A

D7075






1 WEST ELEVATION
1/8" = 1'-0"



2 NORTH ELEVATION
1/8" = 1'-0"


EXTERIOR FINISH SCHEDULE		
Mark	Description	Comments
1	BRICK VENEER	
2	METAL SIDING	
3	CHAIN LINK FENCE	

DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CHK	APP






CITY OF GREAT FALLS, MONTANA
 WATER TREATMENT PLANT
 FACILITY UPGRADES - PHASE 1
 ELECTRICAL ROOM ADDITION
 EXTERIOR ELEVATIONS


DESIGNED:
 DETAILED:
 CHECKED:
 APPROVED:
 DATE:



PROJECT NO.
 O.F. 1519.0
 LPW #12-039



① EAST ELEVATION
1/8" = 1'-0"



② SOUTH ELEVATION
1/8" = 1'-0"

EXTERIOR FINISH SCHEDULE		
Mark	Description	Comments
1	BRICK VENEER	
2	METAL SIDING	
3	CHAIN LINK FENCE	

DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CHK	APP


BLACK & VEATCH

L'Heureux Page Werner


TD&H
 Thomas, Dean & Henderson, Inc.
 Engineering Consultants

CITY OF GREAT FALLS, MONTANA
 WATER TREATMENT PLANT
 FACILITY UPGRADES - PHASE 1
 ELECTRICAL ROOM ADDITION
 EXTERIOR ELEVATIONS

DESIGNED:
 DETAILED:
 CHECKED:
 APPROVED:
 DATE:



PROJECT NO.
 O.F. 1519.0
 LPW #12-039



1 NORTH ELEVATION
1/4" = 1'-0"

EXTERIOR FINISH SCHEDULE		
Mark	Description	Comments
1	BRICK VENEER; TYPE 1	
2	PRE-FINISHED METAL ROOFING TO MATCH EXISTING	
3	PRE-FINISHED METAL SOFFIT TO MATCH EXISTING	
4	BRICK VENEER; TYPE 2	
5	METAL ROOF VENT	

NO.	BY	CHK	APP

DATE	REVISIONS AND RECORD OF ISSUE

USER:	DATE:	VER:

BLACK & VEATCH
B

TD&H
Engineering Consultants
Thomas, Dean & Henkle, Inc.

L'Heureux Page Werner
LPW

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1

ADMINISTRATION BUILDING ADDITION
EXTERIOR ELEVATIONS - ALTERNATE BID ITEM NO. 2

DESIGNED:
DETAILED:
CHECKED:
APPROVED:
DATE:


0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN DRAWING IS
NOT TO FULL SCALE

PROJECT NO.
O.F. 1519.0
LPW #12-039

ALTERNATE BID ITEM NO. 2

AA-3

PL-01-PLC-01



- NOTES:**
1. SEE P&ID LEGEND ON DRAWINGS P-01, P-02, AND P-03.
 2. ALL SYSTEM CODES ARE "CL2" UNLESS OTHERWISE NOTED.
 3. LOCAL CONTROL DEVICES, SUCH AS LIGHTS AND SWITCHES, LOCATED ON MCCs OR AT EQUIPMENT, MAY NOT BE SHOWN ON THIS P&ID.
 4. DRAIN VALVE WITH HOSE CONNECTION.
 5. PIPE SIZES ARE PRELIMINARY AND WILL BE FINALIZED DURING DESIGN.

NO.	BY	CHK	APP

REVISIONS AND RECORD OF ISSUE

DATE

SAVED: XREF1:
 PLOTTED: XREF2:
 USER: XREF3:
 DWG VER: XREF4:

BLACK & VEATCH
 Building a world of difference

TD&H
 Thomas, Dunbar & Heuback, Inc.
 Engineering Consultants

L'Heureux Page Werner

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1

P&ID
 CHLORINE GAS


DESIGNED: BJB
 DETAILED: TSH
 CHECKED:
 APPROVED:
 DATE:

0 1/2 1
 IF THIS BAR DOES NOT
 MEASURE 1" THEN DRAWING IS
 NOT TO FULL SCALE


PROJECT NO.
 177716

I - 1
 SHEET
 OF

TASK 282C



CHEMICAL FEED AND UV DISINFECTION BUILDING
UPPER LEVEL PLAN
 3/16" = 1'-0"



NO.	BY	CHK	APP

DATE	REVISIONS AND RECORD OF ISSUE

WREF1:	WREF2:	WREF3:	WREF4:

SAVED:	PLOTTED:	USER:	DWG. VER.

BLACK & VEATCH
 Building a World of Difference

L'Heureux Page Werner

TD&H
 Engineering Consultants

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1


CHEMICAL FEED AND UV DISINFECTION BUILDING
UPPER LEVEL PLAN

DESIGNED: BJB
 DETAILED: TSH
 CHECKED:
 APPROVED:
 DATE:


PROJECT NO.
 177716

EC-1
 SHEET
 OF


TASK 282C



LOW VOLTAGE SWGR 1 ONE-LINE DIAGRAM
NO SCALE




BACKWASH WATER TREATMENT FACILITIES



ARC EXHAUST PLENUM								
SPACE FOR FUTURE SECTION	MCC-1 FDR (K) ₃ 800AF	SPACE	SPD	ATO CONTROLS	SPD	SPACE	MCC-2 FDR (K) ₃ 800AF	SPACE FOR FUTURE SECTION
	SPARE 800AF	FUTURE BWSP-1 AFD FDR 800AF	METERING		METERING	FUTURE BWSP-2 AFD FDR 800AF	SPARE 800AF	
	SPARE 800AF	FUTURE BWSP-3 AFD FDR 800AF	MCB + CTS 3200AF	TIE CB 3200AF	MCB + CTS 3200AF	FUTURE BWSP-4 AFD FDR 800AF	SPARE 800AF	
	BW TREATMENT FACILITY TRANSFORMER 800AF	LV SWGR 2 FDR 3200AF		GEN CB 3200AF		FUTURE LV SWGR-2B FDR 3200AF	CARBON BLDG TRANSFORMER FDR 800AF	

LOW VOLTAGE SWGR 1 ELEVATION
NO SCALE



NO.	BY	CHK	APP

BLACK & VEATCH
Building a World of Difference

TD&H
Engineering Consultants

L'Heureux Page Werner

DATE: _____
REVISIONS AND RECORD OF ISSUE: _____
SAVED: _____
PLOTTED: _____
USER: _____
DWG. VER: _____

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1


LOW VOLTAGE SWGR 1 ONE-LINE DIAGRAM

DESIGNED: BJB
DETAILED: TSH
CHECKED:
APPROVED:
DATE:

PROJECT NO.
177716

EC-2
SHEET
OF

TASK 282C



MCC-1 AND MCC-2 ONE-LINE DIAGRAM
 (CHEMICAL FEED AND UV DISINFECTION BUILDING)
 NO SCALE


NO.	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	APP.

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1
 MCC-1 AND MCC-2 ONE-LINE DIAGRAM


DESIGNED: BJB
 DETAILED: TSH
 CHECKED:
 APPROVED:
 DATE:

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE

PROJECT NO.
 177716
EC-3
 SHEET OF



ELECTRICAL ROOM ADDITION
(PUMP STATION BUILDING)
3/16" = 1'-0"



NO.	BY	CHK	APP

DATE	REVISIONS AND RECORD OF ISSUE

WREF1:	WREF2:	WREF3:	WREF4:

SAVED:	USER:	DATE:	TIME:

BLACK & VEATCH
Building a World of Difference

L'Heureux Page Werner

TD&H
Engineering Consultants

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1

PUMP STATION BUILDING PLAN
ELECTRICAL ROOM ADDITION
BASE BID


DESIGNED: BJB
DETAILED: TSH
CHECKED:
APPROVED:
DATE:

0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN DRAWING IS
NOT TO FULL SCALE

PROJECT NO.
177716

EP-1
SHEET
OF

TASK 282C



PUMP STATION - LEVEL 1
 1/8" = 1'-0"

NO.	BY	CHK	APP

BLACK & VEATCH
 Building a World of Difference

TD&H
 Thomas, Dorn & Hendrick, Inc.
 Engineering Consultants

L'Heureux Page Werner

DATE: _____
 REVISIONS AND RECORD OF ISSUE:
 WREF1: _____
 WREF2: _____
 WREF3: _____
 WREF4: _____
 SAVER: _____
 PLOTTED: _____
 USER: _____
 DWG. VER: _____

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1

PUMP STATION LEVEL 1

DESIGNED: BJB
 DETAILED: TSH
 CHECKED: _____
 APPROVED: _____
 DATE: _____


0 1/2 1
 IF THIS BAR DOES NOT
 MEASURE 1" THEN DRAWING IS
 NOT TO FULL SCALE

PROJECT NO.
 17716

EP-3
 SHEET
 OF

TASK 282C

FD7000
 07/20



MCC-3 AND MCC-4 ONE-LINE DIAGRAM
(PUMP STATION BUILDING - ELECTRICAL ROOM ADDITION)
NO SCALE

NOTE:
PANEL BOARD AND EQUIPMENT IDENTIFIED WITH SCREENED NAMES ARE EXISTING
PANEL BOARDS AND WILL BE RE-POWERED FROM NEW PANEL BOARDS P1 OR P2.

ALTERNATE BID ITEM NO. 1
NW ENERGY DISCONNECT
& METERING EQUIPMENT
BUILDING

HVAC-ELECTRICAL
ROOM

SPARE
(FUTURE MG SET
MOTOR)

HVAC-PUMP ROOM

P1 ELECTRICAL ROOM
PANEL L4
PANELS P3 & P3A
GARAGE
PANEL-ELECT SHOP
HUGS OFFICE PANEL
SEWAGE EJECTOR
TEMPORARY CKTS AS REQ'D

ELECTRICAL ROOM
LIGHTS &
RECEPTACLES

PUMP ROOM
LIGHTS &
RECEPTACLES

PUMP ROOM
PANEL L2
PANEL L3
PANEL-ELECTRICAL SHOP
PANEL-WORK SHOP
EXCITER #1
PANEL L1

HVAC-PUMP ROOM

HVAC-ELECTRICAL
ROOM

FUTURE
5KV ON-SITE STANDBY POWER
SWGR BLDG FDR
(SUBFEED TO GENSET ENCLOSURE)

NO.	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	APP.

BLACK & VEATCH
Building a World of Difference

TD&H
Engineering Consultants

L'Heureux Page Werner

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1


MCC-3 AND MCC-4 ONE-LINE DIAGRAM

DESIGNED: BJB
DETAILED: TSH
CHECKED:
APPROVED:
DATE:

0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN DRAWING IS
NOT TO FULL SCALE

PROJECT NO.
17716

EP-6
SHEET
OF



DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	APP.



BLACK & VEATCH
Building a World of Difference



TD&H
Engineering Construction



Heureux Page Werner


CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1

 IRRIGATION PUMP
 ONE-LINE DIAGRAM


DESIGNED: BJB
 DETAILED: TSH
 CHECKED:
 APPROVED:
 DATE:

PROJECT NO.
 177716
EP - 7
 SHEET
 OF

TASK 282C



**125VDC MOTOR EXCITATION
POWER DISTRIBUTION ONE-LINE DIAGRAM
(PUMP STATION BUILDING)
NO SCALE**





**125VDC SWITCHGEAR CONTROL POWER
ONE-LINE DIAGRAM
(PUMP STATION BUILDING)
NO SCALE**

FD7000
07026



TASK 282C

DESIGNED: BJB		NO. BY CK APP	
DETAILED: TSH		DATE	
CHECKED:		REVISIONS AND RECORD OF ISSUE	
APPROVED:		DATE	
DATE:		NO. BY CK APP	
PROJECT NO. 177716		REF1:	
EP - 8		REF2:	
SHEET		REF3:	
OF		REF4:	
USER:		DWG. VER:	
 Building a World of Difference		 Theodore Dorn & Heidecker, Inc.	
CITY OF GREAT FALLS, MONTANA WATER TREATMENT PLANT FACILITY UPGRADES - PHASE 1		 L'Heureux Page Werner	
125VDC POWER DISTRIBUTION ONE-LINE DIAGRAMS			



BLACK & VEATCH Building a World of Difference		TD&H Engineering Construction		L'Heureux Page Werner	
CITY OF GREAT FALLS, MONTANA WATER TREATMENT PLANT FACILITY UPGRADES - PHASE 1					
WEST ELECTRICAL SITE PLAN					
DESIGNED: BJB DETAILED: TSH CHECKED: APPROVED: DATE:					
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE					
PROJECT NO. 177716					
GE - 1 SHEET OF					
TASK 282C					

07/20/00
07/20/00



NO.	BY	CHK	APP

DATE	REVISIONS AND RECORD OF ISSUE

SAVED:	REF1:	REF2:	REF3:	REF4:

USER:	PLOTTED:	DATE:	TIME:

BLACK & VEATCH
Building a World of Difference

TD&H
Engineering Consultants

L'Heureux Page Werner

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1



CENTRAL AREA ELECTRICAL
SITE PLAN

DESIGNED: BJB
DETAILED: TSH
CHECKED:
APPROVED:
DATE:

0 1/2 1
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE

PROJECT NO. 177716
GE-2 SHEET OF

TASK 282C



NO.	BY	DATE	REVISIONS AND RECORD OF ISSUE

BLACK & VEATCH
Building a World of Difference

TD&H
Engineering Consultants

L'Heureux Page Werner

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1



EAST AREA ELECTRICAL
SITE PLAN

DESIGNED: BJB
 DETAILED: TSH
 CHECKED:
 APPROVED:
 DATE:

PROJECT NO.
177716

GE-3
SHEET
OF

TASK 282C



NO.	BY	CHK	APP

BLACK & VEATCH
Building a World of Difference

TD&H
Engineering Consultants

L'Heureux Page Werner
L'Heureux Page Werner

CITY OF GREAT FALLS, MONTANA
WATER TREATMENT PLANT
FACILITY UPGRADES - PHASE 1

EAST AREA ELECTRICAL
SITE PLAN

DESIGNED: BJB
DETAILED: TSH
CHECKED:
APPROVED:
DATE:
PROJECT NO. 177716
GE - 3A SHEET OF

TASK 282C

