
Notes:

- 1. The use of "Drop In" risers to achieve final grade is not allowed.
- 2. Three piece riser shall be used. A four piece riser with upward adjustment shall be allowed for deeper valves.
- 3. Engineer may require additional support and rebar anchor system for valves 12" and smaller depending on location and project conditions.
- 4. All bolts, mechanical and flanged joint fittings shall be double wrapped with polyethylene encasement in accordance with AWWA C105, and wrapped with <u>Wax-Tape System</u>.
- 5. 16" or larger sized valves shall be butterfly valves. Operating nut shall be on south or east side of water main. Epoxy coated rebar anchor system required.



STANDARD GATE VALVE DETAIL

OFFICE OF CITY ENGINEER GREAT FALLS, MONTANA

OCT 2011

REVISED: SEPTEMBER 2023

5 - 39